

# ***UNIVERSAL SERVICE***

## **Pacific Bell Cost Proxy Model**

### **Loop Assumptions and Calculations**

DENSITY	SAI \$	% SAI	\$ PER LN	INVESTMENT PER LINE		\$ PER LN	X CONN \$	% X CONN	\$ PER LN	TOTAL \$
				BLDG \$	% BLDG.					
0 - 10	\$57.14	5%	\$2.86	\$75.85	8%	\$6.07	\$81.40	87%	\$70.82	\$79.74
Nov-50	\$45.71	25%	\$11.43	\$39.48	10%	\$3.95	\$75.40	65%	\$49.01	\$64.39
51 - 150	\$38.09	50%	\$19.05	\$28.88	14%	\$4.04	\$31.40	36%	\$11.30	\$34.39
151 - 500	\$21.16	80%	\$16.93	\$23.58	20%	\$4.72	\$ -	0%	N/A	\$21.65
501 - 2000	\$21.16	74%	\$15.66	\$18.65	26%	\$4.85	\$ -	0%	N/A	\$20.51
2001 - 5000	\$21.16	68%	\$14.39	\$18.57	32%	\$5.94	\$ -	0%	N/A	\$20.33
> 5000	\$17.25	47%	\$8.11	\$18.52	53%	\$9.82	\$ -	0%	N/A	\$17.92

# ***UNIVERSAL SERVICE***

## **Pacific Bell Cost Proxy Model**

### **Loop Assumptions and Calculations**

	<b>TERMINALS - INVESTMENTS PER LINE</b>						
	<b>TERMINAL \$</b>		<b>TERMINAL MIX</b>		<b>AVE INVEST</b>	<b>% SINGLE</b>	<b>AVE INVEST</b>
	<b>BURIED</b>	<b>AERIAL</b>	<b>BURIED</b>	<b>AERIAL</b>	<b>SUB TOTAL</b>	<b>FAMILY</b>	<b>SINGLE FAM.</b>
	<b>A</b>	<b>B</b>	<b>C</b>	<b>D</b>	<b>E</b>	<b>F</b>	<b>G</b>
<b>DENSITY</b>					<b>(A*C)+(B*D)</b>		<b>E * F</b>
0 - 10	\$ 481.73	\$ 303.27	60%	40%	\$ 410.35	91%	\$ 373.42
11 - 50	\$ 445.02	\$ 269.86	63%	37%	\$ 380.21	90%	\$ 342.19
51 - 150	\$ 385.51	\$ 227.87	70%	30%	\$ 338.22	86%	\$ 290.87
151 - 500	\$ 276.45	\$ 160.39	70%	30%	\$ 241.63	80%	\$ 193.30
501 - 2000	\$ 108.32	\$ 62.84	85%	15%	\$ 101.50	74%	\$ 75.11
2001-5000	\$ 73.03	\$ 42.37	95%	5%	\$ 71.50	68%	\$ 48.62
5000+	\$ 44.22	\$ 25.66	98%	2%	\$ 43.85	47%	\$ 20.61

# ***UNIVERSAL SERVICE***

## **Pacific Bell Cost Proxy Model**

### **Loop Assumptions and Calculations**

	<b>DROP INVESTMENT PER LINE</b>						
DENSITY	DROP \$		DROP MIX		INVEST	% SINGLE	AVE INVEST
	BURIED	AERIAL	BURIED	AERIAL	SUB TOTAL	FAMILY	SINGLE FAM.
	A	B	C	D	(A*C)+(B*D)	F	F*G
0 - 10	\$ 323.60	\$ 290.82	60%	40%	\$ 310.49	91%	\$ 282.55
11 - 50	\$ 290.33	\$ 261.36	63%	37%	\$ 279.61	90%	\$ 251.65
51 - 150	\$ 236.13	\$ 217.98	70%	30%	\$ 230.68	86%	\$ 198.39
151 - 500	\$ 160.67	\$ 160.68	70%	30%	\$ 160.67	80%	\$ 128.54
501 - 2000	\$ 115.20	\$ 123.19	85%	15%	\$ 116.40	74%	\$ 86.14
2001-5000	\$ 114.22	\$ 123.19	95%	5%	\$ 114.66	68%	\$ 77.97
5001+	\$ 102.23	\$ 113.82	98%	2%	\$ 102.46	47%	\$ 48.16

# UNIVERSAL SERVICE

## Pacific Bell Cost Proxy Model


### Loop Assumptions and Calculations

#### FEEDER < 9000 FEET

#### EXAMPLES

DISTRIBUTION DENSITY 0 - 10


FEEDER DENSITY 11-50



#### FEEDER > 9000 FEET

FEEDER DENSITY 51 - 150

Distribution Density 11 - 50



***UNIVERSAL SERVICE***  
**Pacific Bell Cost Proxy Model**  
**Loop Assumptions and Calculations**

PAIR GAIN EQUIPMENT INVESTMENTS - FRC 257C					
(DIGITAL LOOP CARRIER)					
		FIXED \$	VARIABLE	CHAN.	
	DENSITY	PER LOC	\$ PER PR	CAP.	
	0-10	27800	121	24	
	11-50	34800	271	96	
	51-150	34800	271	96	
	151-500	115000	125	672	
	501-2000	115000	125	672	
	2001-5000	140000	125	1344	
	5001+	140000	125	1344	

**DOES NOT REPRESENT PACIFIC BELL COST**

# UNIVERSAL SERVICE

## Pacific Bell Cost Proxy Model


### Loop Assumptions and Calculations

**FEEDER < 9000 FEET**

**EXAMPLES**

**DISTRIBUTION DENSITY 0-10**

**FEEDER DENSITY 11-50**



**CABLE INVESTMENT** - Length x {(A-Cost + (B Cost x Cable Size)) / Cable Size / Cable Utilization x Modifying Factor}

		<u>INVESTMENT</u>
F	Underground - 3120 x {(3.00 + (.01 x 733)) / 733 / 65% x 1.00} = 3120 x .021681 =	\$67.64
F	Buried - 1280 x {(7.00 + (.01 x 1393)) / 139 / 65% x .90} = 1280 x .083574 =	\$106.98
F	Aerial - 3600 x {(3.00 + (.01 x 190)) / 190 / 65% x 1.00} = 3600 x .039676 =	\$142.83
D	Buried - 1800 x {(7.00 + (.01 x 153)) / 153 / 35% x .80} = 1800 x .127432 =	\$229.38
D	Aerial - 1200 x {(3.00 + (.01 x 66)) / 66 / 35% x 1.00} = 1200 x .158441 =	190.13

**STRUCTURE INVESTMENT** - Length x (Conduit / Cable size / Cable Utilization

F	Conduit	- 3120 x (14.25 / 733 / 65%) = 3120 X .029909 =	\$93.32
	Length x (Poleline / Cable Size / Cable Utilization)		
F	Pole Line	- 3600 x (4.84 / 190 / 65%) = 3600 X .039190 =	\$141.08
D	Pole Line	- 1200 x (4.84 / 66 / 35%) = 1200 X .209524 =	\$251.43

**OTHER INVESTMENT**

SAI -	\$79.74
TERMINAL -	\$373.42
DROP -	\$282.55

**TOTAL INVESTMENT**

DOES NOT REPRESENT PACIFIC BELL COST


**\$1958.50**

# UNIVERSAL SERVICE


## Pacific Bell Cost Proxy Model

### Loop Assumptions and Calculations

**FEEDER > 9000 FEET**



**EXAMPLES**



**FIBER CABLE INVESTMENT** - Length x {(((A-Cost + (B-Cost x Cable Size)) / Cable Size) x 4 Fibers / Cable Utilization x Modifying Factor) / (# of channels x Equipment Utilization)}

		<b><u>INVESTMENT</u></b>
F	Underground - 11700 x {(((2.00 + (.06 x 48)) / 48) x 4 / 67% x 1.00) / (96 x .70%)} = 11700 x .009032 =	\$105.68
F	Buried - 1260 x {(((8.00 + (.06 x 48)) / 48) x 4 / 67% x 1.00) / (96 x .70%)} = 1260 x .020137 =	\$25.37
F	Aerial - 5040 x {(((2.00 + (.06 x 24)) / 48) x 4 / 67% x 1.00) / (96 x .70%)} = 5040 x .012734 =	\$64.18

**STRUCTURE INVESTMENT** - Length x [((Conduit / Cable Size) x 4 Fibers / Cable Utilization) / (Channels x Equipment Utilization)] / 3

F	Conduit - < 9KFT - 9000 x {((17.95 / 48) x 4 / 67%) / (96 x 70%)} / 3 = 9000 x .011074 =	\$99.67
F	Conduit - > 9KFT - 2700 x {((25.30 / 48) x 4 / 67%) / (96 x 70%)} / 3 = 2700 x .015609 =	\$42.14
	Length x {((PoleLine / Cable Size) x 4 Fibers / Cable utilization) / (channels x Equipment Utilization)}	
F	Pole line - 5040 x {((5.45 / 24) x 4 / 67%) / (96 x 70%)} = 5040 x .020174 =	\$101.68

**PAIR GAIN INVESTMENT** - (Fixed Cost & (Variable Cost x Channel Capacity)) / Channel Capacity / Equipment Utilization)

(34,800 & (271 x 96)) / 96 / 70% =

\$905.00

**DISTRIBUTION AGGREGATE**

(Same as Previous Example)

\$1093.19

**TOTAL INVESTMENT**

DOES NOT REPRESENT PACIFIC BELL COST

**\$2436.91**

# UNIVERSAL SERVICE

## Pacific Bell Cost Proxy Model

### Loop Assumptions and Calculations

#### FACTOR DEVELOPMENT for BURIED CABLE

FOR INTERNAL USE ONLY

(A)	(B)	(C=BxJ)	(D)	(E=DxJ)	(F)	(G=FxJ)	(H)	(I=HxJ)	(J)	(K)
<u>CABLE ADJUSTMENT</u>									UNADJ.	AVERAGE
DENSITY	NORMAL	ADJ. \$	MED-DIF (ROCKS)	ADJ. \$	HIGH-DIF (ROCKH)	ADJ. \$	WATER	ADJ. \$	\$ PER SHEATH FOOT	BURIED FEEDER CA. SIZE
0 - 10	1.0	2.46	1.0	2.46	1.0	2.46	1.0	2.46	2.46	96
10 - 50	1.0	2.82	1.0	2.82	1.0	2.82	1.0	2.82	2.82	135
50 - 150	1.0	4.40	1.0	4.40	1.0	4.40	1.0	4.40	4.40	311
150 - 500	1.0	4.14	1.0	4.14	1.0	4.14	1.0	4.14	4.14	282
500 - 2000	1.0	6.19	1.0	6.19	1.0	6.19	1.0	6.19	6.19	510
2000 - 5000	1.1	12.45	1.1	12.45	1.1	12.45	1.1	12.45	11.32	1080
5000 +	1.2	15.57	1.2	15.57	1.2	15.57	1.2	15.57	12.98	1264

FACTORS WERE DEVELOPED TO REFLECT THE AFFECTS OF TERRAIN ON THE TRENCHING OPERATION (\$5.00 PER TRENCH FOOT) AND ADJUSTED INVESTMENTS PER TRENCH FOOT WERE CALCULATED.

(A)	(B)	(C=BxJ)	(D)	(E=DxJ)	(F)	(G=FxJ)	(H)	(I=HxJ)	(J)	(K)
<u>TRENCHING ADJUSTMENT</u>									UNADJ.	AVERAGE
DENSITY	NORMAL	ADJ. \$	MED-DIF (ROCKS)	ADJ. \$	HIGH-DIF (ROCKH)	ADJ. \$	WATER	ADJ. \$	\$ PER TRENCH FOOT	BURIED FEEDER CA. SIZE
0 - 10	0.70	3.50	1.25	6.25	1.75	8.75	1.75	8.75	5.00	96
10 - 50	0.85	4.25	1.40	7.00	1.80	9.00	1.80	9.00	5.00	135
50 - 150	1.00	5.00	1.45	7.25	1.85	9.25	1.85	9.25	5.00	311
150 - 500	1.00	5.00	1.50	7.50	2.00	10.00	2.00	10.00	5.00	282
500 - 2000	1.00	5.00	1.75	8.75	2.50	12.50	2.50	12.50	5.00	510
2000 - 5000	1.10	5.50	2.00	10.00	3.00	15.00	3.00	15.00	5.00	1080
5000 +	1.20	6.00	2.50	12.50	4.00	20.00	4.00	20.00	5.00	1264

THE ADJUSTED PLACING OPERATION INVESTMENTS PER FOOT WERE ADDED TO ADJUSTED TRENCHING COSTS AND SUMS DIVIDED BY THE UNADJUSTED INPLACE COST PER FOOT TO CALCULATE A FACTOR IN EACH DENSITY ZONE AND TERRAIN.

(A)	(B=C/I)	(C)	(D=E/I)	(E)	(F=G/I)	(G)	(H=I/I)	(I)	(J)	(K)
<u>TOTAL ADJUSTMENT</u>									UNADJ.	AVERAGE
DENSITY	NORMAL (mod factor)	ADJ. \$	MED-DIF (ROCKS) (mod factor)	ADJ. \$	HIGH-DIF (ROCKH) (mod factor)	ADJ. \$	WATER (mod factor)	ADJ. \$	\$ PER INPLACE FOOT	BURIED FEEDER CA. SIZE
0 - 10	0.80	5.96	1.17	8.71	1.50	11.21	1.50	11.21	7.46	96
10 - 50	0.90	7.07	1.26	9.82	1.51	11.82	1.51	11.82	7.82	135
50 - 150	1.00	9.40	1.24	11.65	1.45	13.65	1.45	13.65	9.40	311
150 - 500	1.00	9.14	1.27	11.64	1.55	14.14	1.55	14.14	9.14	282
500 - 2000	1.00	11.19	1.34	14.94	1.67	18.69	1.67	18.69	11.19	510
2000 - 5000	1.10	17.95	1.38	22.45	1.68	27.45	1.68	27.45	16.32	1080
5000 +	1.20	21.57	1.56	28.07	1.98	35.57	1.98	35.57	17.98	1264



# UNIVERSAL SERVICE

## Pacific Bell Cost Proxy Model

### Loop Assumptions and Calculations

CONDUIT ( \$ PER DUCT-FOOT ) - FRC 4C  
FOR 0.0 KFT TO 9.0 KFT

REQUIRED DUCTS	A COST	B COST	MOD FACT	MODIFIED A COST	TOTAL B COST	TOTAL INVEST RENCH-FT	NORMAL INVEST. /DUCT-FT
(A)	(B)	(C)	(D)	(E=BxD)	(F=AxC)	(G=E+F)	(H=G/A-1)
3	22.00	2.30	0.80	17.60	6.90	24.50	12.25
3	24.00	2.30	0.90	21.60	6.90	28.50	14.25
3	29.00	2.30	1.00	29.00	6.90	35.90	17.95
3	30.00	2.30	1.00	30.00	6.90	36.90	18.45
4	31.00	2.30	1.05	32.55	9.20	41.75	13.92
6	32.00	2.30	1.10	35.20	13.80	49.00	9.80
9	32.00	2.30	1.25	40.00	20.70	60.70	7.59
REQUIRED DUCTS	A COST	B COST	MOD FACT	MODIFIED A COST	TOTAL B COST	TOTAL INVEST RENCH-FT	MED-DIF INVEST. /DUCT-FT
(A)	(B)	(C)	(D)	(E=BxD)	(F=AxC)	(G=E+F)	(H=G/A-1)
3	22.00	2.30	1.25	27.50	6.90	34.40	17.20
3	24.00	2.30	1.40	33.60	6.90	40.50	20.25
3	29.00	2.30	1.45	42.05	6.90	48.95	24.48
3	30.00	2.30	1.50	45.00	6.90	51.90	25.95
4	31.00	2.30	1.75	54.25	9.20	63.45	21.15
6	32.00	2.30	2.00	64.00	13.80	77.80	15.56
9	32.00	2.30	2.50	80.00	20.70	100.70	12.59
REQUIRED DUCTS	A COST	B COST	MOD FACT	MODIFIED A COST	TOTAL B COST	TOTAL INVEST RENCH-FT	HIGH-DIF INVEST. /DUCT-FT
(A)	(B)	(C)	(D)	(E=BxD)	(F=AxC)	(G=E+F)	(H=G/A-1)
3	22.00	2.30	1.75	38.50	6.90	45.40	22.70
3	24.00	2.30	1.80	43.20	6.90	50.10	25.05
3	29.00	2.30	1.85	53.65	6.90	60.55	30.28
3	30.00	2.30	2.00	60.00	6.90	66.90	33.45
4	31.00	2.30	2.50	77.50	9.20	86.70	28.90
6	32.00	2.30	3.00	96.00	13.80	109.80	21.96
9	32.00	2.30	4.00	128.00	20.70	148.70	18.59
REQUIRED DUCTS	A COST	B COST	MOD FACT	MODIFIED A COST	TOTAL B COST	TOTAL INVEST RENCH-FT	WATER INVEST. /DUCT-FT
(A)	(B)	(C)	(D)	(E=BxD)	(F=AxC)	(G=E+F)	(H=G/A-1)
3	22.00	2.30	1.75	38.50	6.90	45.40	22.70
3	24.00	2.30	1.80	43.20	6.90	50.10	25.05
3	29.00	2.30	1.85	53.65	6.90	60.55	30.28
3	30.00	2.30	2.00	60.00	6.90	66.90	33.45
4	31.00	2.30	2.50	77.50	9.20	86.70	28.90
6	32.00	2.30	3.00	96.00	13.80	109.80	21.96
9	32.00	2.30	4.00	128.00	20.70	148.70	18.59

# UNIVERSAL SERVICE

## Pacific Bell Cost Proxy Model

### Loop Assumptions and Calculations

#### CONDUIT ( \$ PER DUCT-FOOT ) - FRC 4C FOR 9.0 KFT AND LONGER

DENSITY	REQUIRED DUCTS (A)	A COST (B)	B COST (C)	MOD FACT (D)	MODIFIED A COST (E=BxD)	TOTAL B COST (F=AxC)	TOTAL INVEST RENCH-FT (G=E+F)	NORMAL INVEST. /DUCT-FT (H=G/A)
0-10	1	16.00	2.30	0.80	12.80	2.30	15.10	15.10
11-50	1	18.00	2.30	0.90	16.20	2.30	18.50	18.50
51-150	1	23.00	2.30	1.00	23.00	2.30	25.30	25.30
151-500	1	24.00	2.30	1.00	24.00	2.30	26.30	26.30
501-2000	2	25.00	2.30	1.05	26.25	4.60	30.85	15.43
2001-5000	2	26.00	2.30	1.10	28.60	4.60	33.20	16.60
5001+	2	26.00	2.30	1.25	32.50	4.60	37.10	18.55
DENSITY	REQUIRED DUCTS (A)	A COST (B)	B COST (C)	MOD FACT (D)	MODIFIED A COST (E=BxD)	TOTAL B COST (F=AxC)	TOTAL INVEST RENCH-FT (G=E+F)	MED-DIF INVEST. /DUCT-FT (H=G/A)
0-10	1	16.00	2.30	1.25	20.00	2.30	22.30	22.30
11-50	1	18.00	2.30	1.40	25.20	2.30	27.50	27.50
51-150	1	23.00	2.30	1.45	33.35	2.30	35.65	35.65
151-500	1	24.00	2.30	1.50	36.00	2.30	38.30	38.30
501-2000	2	25.00	2.30	1.75	43.75	4.60	48.35	24.18
2001-5000	2	26.00	2.30	2.00	52.00	4.60	56.60	28.30
5001+	2	26.00	2.30	2.50	65.00	4.60	69.60	34.80
DENSITY	REQUIRED DUCTS (A)	A COST (B)	B COST (C)	MOD FACT (D)	MODIFIED A COST (E=BxD)	TOTAL B COST (F=AxC)	TOTAL INVEST RENCH-FT (G=E+F)	HIGH-DIF INVEST. /DUCT-FT (H=G/A)
0-10	1	16.00	2.30	1.75	28.00	2.30	30.30	30.30
11-50	1	18.00	2.30	1.80	32.40	2.30	34.70	34.70
51-150	1	23.00	2.30	1.85	42.55	2.30	44.85	44.85
151-500	1	24.00	2.30	2.00	48.00	2.30	50.30	50.30
501-2000	2	25.00	2.30	2.50	62.50	4.60	67.10	33.55
2001-5000	2	26.00	2.30	3.00	78.00	4.60	82.60	41.30
5001+	2	26.00	2.30	4.00	104.00	4.60	108.60	54.30
DENSITY	REQUIRED DUCTS (A)	A COST (B)	B COST (C)	MOD FACT (D)	MODIFIED A COST (E=BxD)	TOTAL B COST (F=AxC)	TOTAL INVEST RENCH-FT (G=E+F)	WATER INVEST. /DUCT-FT (H=G/A)
0-10	1	16.00	2.30	1.75	28.00	2.30	30.30	30.30
11-50	1	18.00	2.30	1.80	32.40	2.30	34.70	34.70
51-150	1	23.00	2.30	1.85	42.55	2.30	44.85	44.85
151-500	1	24.00	2.30	2.00	48.00	2.30	50.30	50.30
501-2000	2	25.00	2.30	2.50	62.50	4.60	67.10	33.55
2001-5000	2	26.00	2.30	3.00	78.00	4.60	82.60	41.30
5001+	2	26.00	2.30	4.00	104.00	4.60	108.60	54.30

***UNIVERSAL SERVICE***  
**Pacific Bell Cost Proxy Model**  
**Loop Assumptions and Calculations**

DUMMY COST FILE

<u>TYPE OF CABLE</u>	<u>FRC</u>	A COST <u>\$ / SHEATH-FOOT</u>	B COST <u>\$ / PAIR-FOOT</u>
Copper Underground Cable	5C	3.00	0.0100
Copper Buried Cable	4 5C	7.00	0.0100
Copper Aerial Cable	12C	3.00	0.0100
Fiber Underground Cable	85C	2.00	0.0600
Fiber Buried Cable	845C	8.00	0.0600
Fiber Aerial Cable	812C	2.00	0.0600

***UNIVERSAL SERVICE***  
**Pacific Bell Cost Proxy Model**  
**Loop Assumptions and Calculations**

	% FEEDER			
	DISTANCE FROM C.O.			
DENSITY	0-9 KFT	9-15 KFT	15-24 KFT	24 KFT+
0-10	64%	60%	67%	82%
11-50	64%	60%	67%	82%
51-150	64%	60%	73%	85%
151-500	64%	73%	86%	92%
501-2000	68%	83%	89%	90%
2001-5000	77%	85%	89%	93%
5001+	85%	89%	93%	93%

**COST PROXY MODEL**

PAGE 1.0

**FEEDER AND DISTRIBUTION CABLES****% MIX BY DENSITY ZONES**

<b>DENSITY</b>	<b>COPPER FEEDER &lt;9000'</b>			<b>FIBER FEEDER &gt;9000'</b>			<b>COPPER DISTRIBUTION</b>		
	<b>UG</b>	<b>BURIED</b>	<b>AERIAL</b>	<b>UG</b>	<b>BURIED</b>	<b>AERIAL</b>	<b>UG</b>	<b>BURIED</b>	<b>AERIAL</b>
0-10	21%	27%	52%	21%	27%	52%	0%	60%	40%
11-50	39%	16%	45%	39%	16%	45%	3%	60%	37%
51-150	66%	7%	27%	66%	7%	27%	5%	65%	30%
151-500	81%	3%	16%	81%	3%	16%	5%	65%	30%
501-2000	94%	1%	5%	94%	1%	5%	15%	70%	15%
2001-5000	97%	0.5%	2.5%	97%	0.5%	2.5%	20%	75%	5%
5001+	98.5%	0.5%	1%	98.5%	0.5%	1%	88%	10%	2%

**ASSUMPTIONS**

- 1 ) The % mix for copper feeder cables was developed from PLAN feeder information on feeder sections under 9000 feet. The mix by density zone was developed by sorting the feeder information by the density of the wire centers.
- 2 ) The % mix for fiber feeder cables were assumed to be the same as the copper feeder cables.
- 3 ) The % mix by density zones for copper distribution cable was based on the following:
  - CPUC and local regulations which emphasize "out of sight" plant.
  - Buried distribution cable is first choice except in cases where terrain type would drive excessive costs.

**COST PROXY MODEL**

PAGE 2.0

**FEEDER AND DISTRIBUTION CABLES****AVERAGE CABLE SIZES BY DENSITY ZONES**

<b>DENSITY</b>	<b>COPPER FEEDER &lt;9000'</b>			<b>FIBER FEEDER &gt;9000'</b>			<b>COPPER DISTRIBUTION</b>		
	<b>UG</b>	<b>BURIED</b>	<b>AERIAL</b>	<b>UG</b>	<b>BURIED</b>	<b>AERIAL</b>	<b>UG</b>	<b>BURIED</b>	<b>AERIAL</b>
0-10	774	111	143	48	48	24	323	153	66
11-50	952	182	248	48	48	24	243	298	201
51-150	1280	379	446	48	48	24	305	255	234
151-500	1708	400	577	48	48	24	543	284	337
501-2000	2025	720	835	48	48	24	526	266	377
2001-5000	2426	1333	1256	48	48	24	561	302	410
5001+	2712	1649	1356	48	48	24	599	386	414

**ASSUMPTIONS**

1 ) The average sizes for copper feeder cables were developed from PLAN feeder information on feeder sections under 9000 feet. The copper feeder cables in these sections were resized to reflect the reduced copper demand in the sections due to the forward looking policy to serve all services with feeder lengths over 9000 feet via fiber.

2 ) The average size fiber cables were based on the sizes of the fiber cables placed during 1991 to 1994

Underground fiber cable	85C	42.42 fibers
Buried fiber cable	845C	49.65 fibers
Aerial fiber cable	812C	20.86 fibers

3 ) The average cable sizes for copper distribution cables were developed from the 1995 loop samples taken for OANAD study.

## COST PROXY MODEL

PAGE 3.0

## AVERAGE UTILIZATION % BY DENSITY ZONES

DENSITY	COPPER FEEDER	FIBER FEEDER	PAIR-GAIN EQUIP.	DISTRIBUTION
	AVG UTILIZATION	AVG UTILIZATION	AVG UTILIZATION	AVG UTILIZATION
0-10	53%	67%	69%	36%
11-50	59%	67%	71%	36%
51-150	64%	67%	71%	37%
151-500	66%	67%	68%	38%
501-2000	68%	67%	66%	39%
2001-5000	67%	67%	63%	39%
5001+	59%	67%	66%	40%

**ASSUMPTIONS**

The above utilization percentages are derived as follows :

## 1 ) Average Utilization Levels

Copper Feeder = EOY 94' actual utilization levels by density zone.

Fiber Feeder = Utilization levels based on a forward looking view of a residential network using 4 fibers per remote terminal system (2 fibers for transmit and receive and 2 fibers for protection).

Pair-Gain (Equipped) = EOY 94' actual utilization levels by density zone that measures working channels to the equipped capacity of the Remote Terminal (RT) - "Ready to Serve" (equipped with plug-ins).

Copper Distribution = Distribution plant is sized for two pairs per unit. The smallest standard cable size that covers this requirement is placed. These utilization levels also reflect second line usage by density zone.

The average utilization percentages were developed from information obtained from the EOY 1994 DCAS REPORT and were sorted into density zones using the 1994 densities for each wire center.

**COST PROXY MODEL**

PAGE 4.0

**DISTRIBUTION POLE LINE ( \$ PER LINEAR FOOT ) - FRC 1C**

<b>DENSITY</b>	<b>NORMAL</b>	<b>MED-DIF (ROCKS)</b>	<b>HIGH-DIF (ROCKH)</b>	<b>WATER</b>
0-10	4.84	4.96	5.69	4.96
11-50	4.84	4.96	5.69	4.96
51-150	5.45	5.69	6.42	5.69
151-500	5.45	5.69	6.42	5.69
501-2000	4.02	4.02	4.02	4.02
2001-5000	4.02	4.02	4.02	4.02
5001+	4.02	4.02	4.02	4.02

**ASSUMPTIONS**

1 ) The following assumptions were used for aerial plant placements using a "forward looking" philosophy:

- 1.1 The urban areas (densities over 500) would be buried or underground plant except in cases where pole line costs would be shared with other utilities ( joint pole agreements ).
- 1.2 The rural areas (densities 0 to 500) would be a combination of solely and jointly owned poles when buried plant was not feasible. The cost tables for 0 - 500 were based on 25% solely owned and 75% jointly owned poles.

2 ) Solely Owned Poles

- 2.1 Investments for solely owned poles were developed using the \$9.73 per foot of pole line from the PLAN/ESM cost deck and adjusted for density zone and type of terrain:
- 2.2 Modified the \$9.73 per foot for solely owned poles for density:
  - in density zones under 50 access lines per square mile, the modifying factors were developed to reflect lower costs for spotting material, easier work site access, less pavement, and less substructure congestion.
  - in density zones between 50 and 500 access lines per square mile, the modifying factors reflect normal placing costs.
- 2.3 Modified the \$9.73 per foot for solely owned poles by terrain:
  - no modification in "normal terrain."
  - modification factors in "med-difficulty terrain" reflect the increased placing costs due to hard or rocky soil.
  - modification factors in "high-difficulty terrain" reflect the increased placing costs due solid rock.
  - modification factors in "water" reflect costs similar to med-difficulty.



**Modified Investments for Solely Owned Poles**

<u>Density Zone</u>	<u>Mod. Fact.</u>	<u>Normal Terrain</u>	<u>Mod. Fact.</u>	<u>Med-Difficulty Terrain</u>	<u>Mod. Fact.</u>	<u>High-Difficulty Terrain</u>	<u>Mod. Fact.</u>	<u>Water</u>
0-10	0.75	\$7.30	0.80	\$7.78	1.10	\$10.70	0.80	\$7.78
11-50	0.75	\$7.30	0.80	\$7.78	1.10	\$10.70	0.80	\$7.78
51-150	1.00	\$9.73	1.10	\$10.70	1.40	\$13.62	1.10	\$10.70
151-500	1.00	\$9.73	1.10	\$10.70	1.40	\$13.62	1.10	\$10.70

**3 ) Jointly Owned Poles**

3.1 The investments for jointly owned pole line were developed using the purchase prices for poles and anchors from the Joint Pole Agreement with PG&E.

3.2 The cost were based on a 45' pole and a 23' attachment :  
 - joint pole purchase price is \$603  
 - joint screw anchor for 6M guy purchase price is \$115  
 - placement cost of 6M guy is \$86 (from PLAN/ESM cost deck)

3.3 Pole line cost per linear foot is based on 6 joint poles, 2 joint anchors, and 2 guys every 1000 feet.

**CALCULATION OF JOINTLY OWNED POLE LINE COST PER LINEAR FOOT**

6	Joint Poles	@	\$603	=	\$3,618
2	Joint Anchors	@	\$115	=	\$230
2	Joint Guys	@	\$86	=	\$172
TOTAL for 1000 ft.					<u>\$4,020</u>
\$4,020 / 1000 feet					= \$4.02

**4 ) Summarization of Pole Line Investments****Normal Terrain - Density 0 -10**

<u>Type</u>	<u>Investment</u>		<u>% Occurrence</u>		<u>Weighted Investment</u>
Solely Owned Poles	\$7.30	x	25%	=	\$1.83
Jointly Owned Poles	\$4.02	x	75%	=	\$3.02
<b>Melded Investment</b>					<u><b>\$4.84</b></u>

**High-Difficulty Terrain - Density 50 -150**

<u>Type</u>	<u>Investment</u>		<u>% Occurrence</u>		<u>Weighted Investment</u>
Solely Owned Poles	\$13.62	x	25%	=	\$3.41
Jointly Owned Poles	\$4.02	x	75%	=	\$3.02
<b>Melded Investment</b>					<u><b>\$6.42</b></u>

**COST PROXY MODEL**

PAGE 4.2

**FEEDER POLE LINE ( \$ PER LINEAR FOOT ) - FRC 1C**

<b>DENSITY</b>	<b>NORMAL</b>	<b>MED-DIF (ROCKS)</b>	<b>HIGH-DIF (ROCKH)</b>	<b>WATER</b>	<b>2nd CABLE FACTOR</b>
0-10	4.81	4.93	5.65	4.93	0.9935
11-50	4.79	4.91	5.63	4.91	0.9898
51-150	5.29	5.53	6.24	5.53	0.9720
151-500	5.19	5.42	6.11	5.42	0.9524
501-2000	3.58	3.58	3.58	3.58	0.8899
2001-5000	3.19	3.19	3.19	3.19	0.7926
5001+	2.89	2.89	2.89	2.89	0.7179

**ASSUMPTIONS**

1 ) The following assumptions were used for aerial plant placements using a "forward looking" philosophy:

- 1.1 The urban areas (densities over 500) would be buried or underground plant except in cases where pole line costs would be shared with other utilities ( joint pole agreements ).
- 1.2 The rural areas (densities 0 to 500) would be a combination of solely and jointly owned poles when buried plant was not feasible. The cost tables for 0 - 500 were based on 25% solely owned and 75% jointly owned poles

2 ) Solely Owned Poles

- 2.1 Investments for solely owned poles were developed using the \$9.73 per foot of pole line from the PLAN/ESM cost deck and adjusted for density zone and type of terrain
- 2.2 Modified the \$9.73 per foot for solely owned poles for density:
  - in density zones under 50 access lines per square mile, the modifying factors were developed to reflect lower costs for spotting material, easier work site access, less pavement, and less substructure congestion.
  - in density zones between 50 and 500 access lines per square mile, the modifying factors reflect normal placing costs.
- 2.3 Modified the \$9.73 per foot for solely owned poles by terrain:
  - no modification in "normal terrain.
  - modification factors in "med-difficulty terrain" reflect the increased placing costs due to hard or rocky soil.
  - modification factors in "high-difficulty terrain" reflect the increased placing costs due solid rock.
  - modification factors in "water" reflect costs similar to med-difficulty.

3 ) Second Cable on the Pole Line

- 3.1 The percent occurrence of a second cable on a pole line was based on the % of the aerial feeder that would require a cable over 1500 pairs. 1500 pairs is the largest aerial cable that would be placed. A second cable factor was developed by dividing 1 by 1 plus the percentage [  $1 / ( 1 + \% )$  ]

**Modified Investments for Solely Owned Poles**

PAGE 4.3

<u>Density Zone</u>	<u>Mod. Fact.</u>	<u>Normal Terrain</u>	<u>Mod. Fact.</u>	<u>Med-Diff. Terrain</u>	<u>Mod. Fact.</u>	<u>High-Diff. Terrain</u>	<u>Mod. Fact.</u>	<u>Water</u>
0-10	0.75	\$7.30	0.80	\$7.78	1.10	\$10.70	0.80	\$7.78
11-50	0.75	\$7.30	0.80	\$7.78	1.10	\$10.70	0.80	\$7.78
51-150	1.00	\$9.73	1.10	\$10.70	1.40	\$13.62	1.10	\$10.70
151-500	1.00	\$9.73	1.10	\$10.70	1.40	\$13.62	1.10	\$10.70

**3 ) Jointly Owned Poles**

3.1 The investments for jointly owned pole line were developed using the purchase prices for poles and anchors from the Joint Pole Agreement with PG&E.

3.2 The cost were based on a 45' pole and a 23' attachment :

- joint pole purchase price is \$603
- joint screw anchor for 6M guy purchase price is \$115
- placement cost of 6M guy is \$86 (from PLAN/ESM cost deck)

3.3 Pole line cost per linear foot is based on 6 joint poles, 2 joint anchors, and 2 guys every 1000 feet.

**CALCULATION OF JOINTLY OWNED  
POLE LINE COST PER LINEAR FOOT**

Joint Poles	6 @	\$603	=	\$3,618
Joint Anchors	2 @	\$115	=	\$230
Joint Guys	2 @	\$86	=	\$172
TOTAL for 1000 ft.				\$4,020
\$4,020	/	1000 feet	=	\$4.02

**CALCULATION OF 2nd CABLE FACTOR**

<u>ZONE #</u>	<u>%</u>	<u>FACTOR</u>
1	0.65%	0.9935
2	1.03%	0.9898
3	2.88%	0.9720
4	5.00%	0.9524
5	12.37%	0.8899
6	26.16%	0.7926
7	39.29%	0.7179

**4 ) Summarization of Pole Line Investments**

**Normal Terrain - Density 0 -10**

<u>Type</u>	<u>Investment</u>	<u>% Occurrence</u>	<u>Weighted Investment</u>	<u>2nd Cable Factor</u>	<u>Total Investment</u>
Solely Owned Poles	\$7.30	x 25%	= \$1.83		
Jointly Owned Pole	\$4.02	x 75%	= \$3.02		
			<u>\$4.84</u>	0.9935	<b>\$4.81</b>

**High-Difficulty Terrain - Density 50 -150**

<u>Type</u>	<u>Investment</u>	<u>% Occurrence</u>	<u>Weighted Investment</u>	<u>2nd Cable Factor</u>	<u>Total Investment</u>
Solely Owned Poles	\$13.62	x 25%	= \$3.41		
Jointly Owned Pole	\$4.02	x 75%	= \$3.02		
			<u>\$6.42</u>	0.972	<b>\$6.24</b>

**COST PROXY MODEL**

PAGE 5 0

**CONDUIT ( \$ PER DUCT-FOOT ) - FRC 4C  
FOR 0.0 KFT TO 9.0 KFT**

<b>DENSITY</b>	<b>NORMAL</b>	<b>MED-DIF (ROCK-S)</b>	<b>HIGH-DIF (ROCK-H)</b>	<b>WATER</b>
0-10	12.25	17.20	22.70	22.70
11-50	14.25	20.25	25.05	25.05
51-150	17.95	24.48	30.28	30.28
151-500	18.45	25.95	33.45	33.45
501-2000	13.92	21.15	28.90	28.90
2001-5000	9.80	15.56	21.96	21.96
5001+	7.59	12.59	18.59	18.59

NOTE: The reduction in the cost per duct-foot in the three highest density zones reflects the requirement of more ducts which share the trenching cost.

**ASSUMPTIONS**

- 1 ) The above investments per duct foot were developed using the "A Cost" and "B Cost" from the PLAN/ESM cost deck and the number of ducts that would typically be required in each density zone and providing a spare maintenance duct, ducts for fiber, and air pipe.
- 2 ) "A Cost" includes :
  - engineering labor
  - inspection labor
  - travel time
  - set-up time
  - inplace cost of underground vaults ( typical size 8 1/2 x 4 1/2 x 6 1/2 ) spaced at 600 feet
  - cut & replace @ \$10/ft ( added to each density zone by estimated % of occurrence )
- 3 ) "B Cost" includes :
  - material cost of ducts
  - labor for placement of ducts
- 4 ) modified "A Cost" by density zone for :
  - material spotting becomes more difficult and costly as the density of the work area increases
  - substructure congestion increases with density and causes delays and changes
  - heavier traffic in denser areas increases the required lane controls and work area protection
  - frequency of street crossings that increases the amount of cutting and repaving required as well as restricting the length of trench that can be opened at one time
  - work hour restrictions are usually imposed in denser areas primarily do to commuter traffic

**CONDUIT ( \$ PER DUCT-FOOT ) - FRC 4C**

PAGE 5.1

**FOR 0.0 KFT TO 9.0 KFT**

FACTORS WERE ESTIMATED FOR EACH DENSITY ZONE AND TERRAIN TO REFLECT THE CONDITIONS LISTED IN ASSUMPTION # 4 AND APPLIED TO THE "A COST". THE "B COST" WAS ADDED TO GET THE TOTAL INVESTMENT PER TRENCH-FOOT WHICH WAS DIVIDED BY THE NUMBER OF DUCTS MINUS ONE MAINTENANCE DUCT TO DETERMINE THE INVESTMENT / DUCT-FOOT.

DENSITY	REQUIRED DUCTS (A)	A COST (B)	B COST (C)	MOD FACT (D)	MODIFIED A COST (E=BxD)	TOTAL B COST (F=AxC)	TOTAL INVEST TRENCH-FT (G=E+F)	NORMAL INVEST. /DUCT-FT (H=G/A-1)
0-10	3	22.00	2.30	0.80	17.60	6.90	24.50	12.25
11-50	3	24.00	2.30	0.90	21.60	6.90	28.50	14.25
51-150	3	29.00	2.30	1.00	29.00	6.90	35.90	17.95
151-500	3	30.00	2.30	1.00	30.00	6.90	36.90	18.45
501-2000	4	31.00	2.30	1.05	32.55	9.20	41.75	13.92
2001-5000	6	32.00	2.30	1.10	35.20	13.80	49.00	9.80
5001+	9	32.00	2.30	1.25	40.00	20.70	60.70	7.59
DENSITY	REQUIRED DUCTS (A)	A COST (B)	B COST (C)	MOD FACT (D)	MODIFIED A COST (E=BxD)	TOTAL B COST (F=AxC)	TOTAL INVEST TRENCH-FT (G=E+F)	MED-DIF INVEST. /DUCT-FT (H=G/A-1)
0-10	3	22.00	2.30	1.25	27.50	6.90	34.40	17.20
11-50	3	24.00	2.30	1.40	33.60	6.90	40.50	20.25
51-150	3	29.00	2.30	1.45	42.05	6.90	48.95	24.48
151-500	3	30.00	2.30	1.50	45.00	6.90	51.90	25.95
501-2000	4	31.00	2.30	1.75	54.25	9.20	63.45	21.15
2001-5000	6	32.00	2.30	2.00	64.00	13.80	77.80	15.56
5001+	9	32.00	2.30	2.50	80.00	20.70	100.70	12.59
DENSITY	REQUIRED DUCTS (A)	A COST (B)	B COST (C)	MOD FACT (D)	MODIFIED A COST (E=BxD)	TOTAL B COST (F=AxC)	TOTAL INVEST TRENCH-FT (G=E+F)	HIGH-DIF INVEST. /DUCT-FT (H=G/A-1)
0-10	3	22.00	2.30	1.75	38.50	6.90	45.40	22.70
11-50	3	24.00	2.30	1.80	43.20	6.90	50.10	25.05
51-150	3	29.00	2.30	1.85	53.65	6.90	60.55	30.28
151-500	3	30.00	2.30	2.00	60.00	6.90	66.90	33.45
501-2000	4	31.00	2.30	2.50	77.50	9.20	86.70	28.90
2001-5000	6	32.00	2.30	3.00	96.00	13.80	109.80	21.96
5001+	9	32.00	2.30	4.00	128.00	20.70	148.70	18.59
DENSITY	REQUIRED DUCTS (A)	A COST (B)	B COST (C)	MOD FACT (D)	MODIFIED A COST (E=BxD)	TOTAL B COST (F=AxC)	TOTAL INVEST TRENCH-FT (G=E+F)	WATER INVEST. /DUCT-FT (H=G/A-1)
0-10	3	22.00	2.30	1.75	38.50	6.90	45.40	22.70
11-50	3	24.00	2.30	1.80	43.20	6.90	50.10	25.05
51-150	3	29.00	2.30	1.85	53.65	6.90	60.55	30.28
151-500	3	30.00	2.30	2.00	60.00	6.90	66.90	33.45
501-2000	4	31.00	2.30	2.50	77.50	9.20	86.70	28.90
2001-5000	6	32.00	2.30	3.00	96.00	13.80	109.80	21.96

5001+	9	32.00	2.30	4.00	128.00	20.70	148.70	18.59
-------	---	-------	------	------	--------	-------	--------	-------

## CONDUIT ( \$ PER DUCT-FOOT ) - FRC 4C

PAGE 5.2

**SAMPLE CALCULATION  
OF \$ PER DUCT-FOOT  
FOR "NORMAL TERRAIN - DENSITY 5000+**

(A)	"A COST"	\$22.00	( PER TRENCH FOOT)
(B)	CUT & REPLACE PAVEMENT	+ \$10.00	( PER TRENCH FOOT)
(C)	SUB-TOTAL	<u>\$32.00</u>	( PER TRENCH FOOT)
(D)	MODIFYING FACTOR	x <u>1.25</u>	
(E=CxD)	TRENCHING COST (\$32.00 x 1.25)	<b>\$40.00</b>	( PER TRENCH FOOT)
(F)	"B COST"	\$2.30	(PER DUCT-FOOT)
(G)	NUMBER OF DUCTS	x <u>9</u>	
(H=FxG)	DUCT COST (9 x \$2.30)	<b>\$20.70</b>	( PER TRENCH FOOT)
(I=E+H)	TOTAL CONDUIT COST (\$40.00+\$20.70)	<b>\$60.70</b>	( PER TRENCH FOOT)
(J)	USABLE DUCTS (9 - 1) (ONE DUCT MUST REMAIN SPARE FOR MAINTENANCE)	8	
(K=I/J)	COST PER DUCT-FOOT	<b>\$7.59</b>	

**COST PROXY MODEL**

PAGE 6.0

**4C - CONDUIT ( \$ PER DUCT-FOOT )  
FOR 9.0 KFT AND LONGER**

<b>DENSITY</b>	<b>NORMAL</b>	<b>MED-DIF (ROCK-S)</b>	<b>HIGH-DIF (ROCK-H)</b>	<b>WATER</b>
0-10	15.10	22.30	30.30	30.30
11-50	18.50	27.50	34.70	34.70
51-150	25.30	35.65	44.85	44.85
151-500	26.30	38.30	50.30	50.30
501-2000	15.43	24.18	33.55	33.55
2001-5000	16.60	28.30	41.30	41.30
5001+	18.55	34.80	54.30	54.30

**NOTE:** The reduction in the cost per duct-foot in the three highest density zones is caused by the increase in the number of ducts required, therefore trenching costs are spread over more ducts.

**ASSUMPTIONS**

- 1 ) The above investments per duct foot were developed using the "A Cost" and "B Cost" from the PLAN cost deck and the number of ducts that would typically be required in each density zone.
- 2 ) "A Cost" includes :
  - engineering labor
  - inspection labor
  - travel time
  - set-up time
  - inplace cost of underground vaults ( typical size 8 1/2 x 4 1/2 x 6 1/2 ) spaced at 600 feet
  - cut & replace @ \$10/ft ( added to each density zone by estimated % of occurrence )
- 3 ) "B Cost" includes :
  - material cost of ducts
  - labor for placement of ducts
- 4 ) modified "A Cost" by density zone for :
  - material spotting becomes more difficult and costly as the density of the work area increases
  - substructure congestion increases with density and causes delays and changes
  - heavier traffic in denser areas increases the required lane controls and work area protection
  - frequency of street crossings that increases the amount of cutting and repaving required as well as restricting the length of trench that can be opened at one time
  - work hour restrictions are usually imposed in denser areas primarily do to commuter traffic



**CONDUIT ( \$ PER DUCT-FOOT ) - FRC 4C**  
**FOR 9.0 KFT AND LONGER**

FACTORS WERE ESTIMATED FOR EACH DENSITY ZONE AND TERRAIN TO REFLECT THE CONDITIONS LISTED IN ASSUMPTION # 4 AND APPLIED TO THE "A COST". THE "B COST" WAS ADDED TO GET THE TOTAL INVESTMENT PER TRENCH-FOOT WHICH WAS DIVIDED BY THE NUMBER OF DUCTS. THE "A COST" REFLECT ADJUSTMENT FOR 1500 FOOT SPLICE VAULT SPACING.

DENSITY	REQUIRED DUCTS (A)	A COST (B)	B COST (C)	MOD FACT (D)	MODIFIED A COST (E=BxD)	TOTAL B COST (F=AxC)	TOTAL INVEST TRENCH-FT (G=E+F)	NORMAL INVEST. /DUCT-FT (H=G/A)
0-10	1	16.00	2.30	0.80	12.80	2.30	15.10	15.10
11-50	1	18.00	2.30	0.90	16.20	2.30	18.50	18.50
51-150	1	23.00	2.30	1.00	23.00	2.30	25.30	25.30
151-500	1	24.00	2.30	1.00	24.00	2.30	26.30	26.30
501-2000	2	25.00	2.30	1.05	26.25	4.60	30.85	15.43
2001-5000	2	26.00	2.30	1.10	28.60	4.60	33.20	16.60
5001+	2	26.00	2.30	1.25	32.50	4.60	37.10	18.55
DENSITY	REQUIRED DUCTS (A)	A COST (B)	B COST (C)	MOD FACT (D)	MODIFIED A COST (E=BxD)	TOTAL B COST (F=AxC)	TOTAL INVEST TRENCH-FT (G=E+F)	MED-DIF INVEST. /DUCT-FT (H=G/A)
0-10	1	16.00	2.30	1.25	20.00	2.30	22.30	22.30
11-50	1	18.00	2.30	1.40	25.20	2.30	27.50	27.50
51-150	1	23.00	2.30	1.45	33.35	2.30	35.65	35.65
151-500	1	24.00	2.30	1.50	36.00	2.30	38.30	38.30
501-2000	2	25.00	2.30	1.75	43.75	4.60	48.35	24.18
2001-5000	2	26.00	2.30	2.00	52.00	4.60	56.60	28.30
5001+	2	26.00	2.30	2.50	65.00	4.60	69.60	34.80
DENSITY	REQUIRED DUCTS (A)	A COST (B)	B COST (C)	MOD FACT (D)	MODIFIED A COST (E=BxD)	TOTAL B COST (F=AxC)	TOTAL INVEST TRENCH-FT (G=E+F)	HIGH-DIF INVEST. /DUCT-FT (H=G/A)
0-10	1	16.00	2.30	1.75	28.00	2.30	30.30	30.30
11-50	1	18.00	2.30	1.80	32.40	2.30	34.70	34.70
51-150	1	23.00	2.30	1.85	42.55	2.30	44.85	44.85
151-500	1	24.00	2.30	2.00	48.00	2.30	50.30	50.30
501-2000	2	25.00	2.30	2.50	62.50	4.60	67.10	33.55
2001-5000	2	26.00	2.30	3.00	78.00	4.60	82.60	41.30
5001+	2	26.00	2.30	4.00	104.00	4.60	108.60	54.30
DENSITY	REQUIRED DUCTS (A)	A COST (B)	B COST (C)	MOD FACT (D)	MODIFIED A COST (E=BxD)	TOTAL B COST (F=AxC)	TOTAL INVEST TRENCH-FT (G=E+F)	WATER INVEST. /DUCT-FT (H=G/A)
0-10	1	16.00	2.30	1.75	28.00	2.30	30.30	30.30
11-50	1	18.00	2.30	1.80	32.40	2.30	34.70	34.70
51-150	1	23.00	2.30	1.85	42.55	2.30	44.85	44.85
151-500	1	24.00	2.30	2.00	48.00	2.30	50.30	50.30
501-2000	2	25.00	2.30	2.50	62.50	4.60	67.10	33.55
2001-5000	2	26.00	2.30	3.00	78.00	4.60	82.60	41.30