EX PARTE OR LATE FILED

DOCKET FILE COPY ORIGINAL



Warren D. Hannah Director, Federal Regulatory Relations 1850 M Street, NW, Ste. 1100 Washington, DC 20036 Telephone (202) 828-7452 Fax (202) 296-3469

SUPPLEMENTAL EX PARTE

June 5, 1997

RECEIVED

Mr. William F. Caton Acting Secretary Federal Communications Commission 1919 M Street, N.W. Room 222 Washington, D.C. 20554

JUN - 5 1997

Federal Communications Commission
Office of Secretary

RE:

In the Matter of Federal-State Joint Board on Universal Service -

CC Docket No. 96-45

Dear Mr. Caton,

Sprint conducted an Ex Parte presentation in the above referenced docket on March 24, 1997. A copy of the material used in the March 24, 1997, meeting is attached. The information presented during the meeting represented input information to the Benchmark Cost Proxy Model (BCPM) and positions of Sprint Corporation only.

During a recent review of the March 24, 1997, information, an input error was discovered. The input error does not affect the structural integrity of the BCPM.

As referenced on page 3 of Attachment A to the Ex Parte, Sprint intended to reduce the BCPM default costs for copper and fiber material by 20 percent. However, the actual material cost used in the exhibit contained discounts considerably above the intended twenty percent level. The input error is visible on pages 1 and 2 of the attachment labeled as "ATTACHMENT - Sprint Revised Input Values" and only impacts cable and wire cost information displayed on the two pages. For example, the amount displayed on page 1 for Cable Size - 3600, FCC Filing, Cost Underground, is \$33.30. As stated in the Ex Parte, Sprint proposed a 20 percent reduction in these costs to more accurately reflect known cost information. The input information shown on the above referenced line labeled "Sprint Run" reflects an erroneous input as a 40 percent reduction (discount) for cable and wire investment cost. This input is easily correctable and was intended as a temporary input to the BCPM to assist the Commission in reaching its May 8, 1997, decision in this matter.

No. of Copies rec'd C+ | List ABCDE Mr. William F. Caton June 5, 1997 Page 2

Sprint requests that this information be made a part of the record in this matter. Two copies of this letter, in accordance with Section 1.1206(a)(1), is provided for this purpose. If there are any questions, please feel free to call.

Sincerely,

Warren D. Hannah

Attachment

c: Attendees



Warren D. Hannah Director, Federal Regulatory Relations

1850 M Street, NW, Ste. 1100 Washington, DC 20036 Telephone (202) 828-7452 Fax (202) 296-3469

EX PARTE

March 24, 1997

Mr. William F. Caton
Acting Secretary
Federal Communications Commission
1919 M Street, N.W. Room 222
Washington, D.C. 20554

RE: In the Matter of Federal-State Joint Board on Universal Service - CC Docket No. 96-45

Dear Mr. Caton,

On Friday, March 21, 1997, representatives of Sprint Corporation met with members of the Commission's Common Carrier Bureau and Office of General Counsel to discuss the use of proxy cost models in the above referenced proceeding. Representing the Commission were:

John Nakahata C. Anthony Bush Brian Clopton Bob Loube Jeanine Poltronieri Bill Sharkey

Brad Wimmer

Representing Sprint were:

Jim Dunbar Warren Hannah Jay Keithley

Jim Sichter

Attachment A is a copy of the materials used in the meeting. Sprint urges the Commission to adopt the BCPM as the platform model for determining USF funding. The materials present Sprint's proposal for accomplishing this objective. The information provides results of the BCPM "run" with Sprint proposed inputs. This proposal, and the model input changes, represent the position of Sprint Corporation only, and not that of the other BCPM model sponsors.

Mr. William F. Caton March 24, 1997 Page 2

On page 4 of Attachment A, Sprint adds paragraph 6 as follows:

6. Sprint also used a fiber/copper breakpoint of 15,000 feet and a maximum length of copper cable in the CBG distribution area of 18,000 feet. Both of these values are the same as requested in the Federal-State Joint Board staff's latest request.

Attachment B, "Miscellaneous Inputs" page was inadvertently left out of the materials used in the meeting.

Finally, during the meeting a letter from Rockwell Semiconductor Systems was discussed and is labeled Attachment C. Any proxy model selected by the Commission should ensure that the attributes discussed in this letter are included. The BCPM meets the criteria discussed in the letter.

Sprint requests that this information be made a part of the record in this matter. Two copies of this letter, in accordance with Section 1.1206(a)(1), is provided for this purpose. If there are any questions with regard to this notice, please feel free to call.

Sincerely,

Warren D. Hannah

Attachments

c: Attendees



Attachment A

SPRINT PROPOSAL FOR USING PROXY MODEL RESULTS FOR USF

In its Recommended Decision, issued November 8, 1996, the Joint Board recommended the use of a proxy model for the purpose of determining USF costs. In recent weeks, public comments by the Commission have expressed dissatisfaction with the proxy models that have been placed on the public record, and have suggested that it is considering an interim USF plan that would not rely on proxy model results.

Sprint disagrees with that assessment of proxy models, at least in respect to the Benchmark Cost Proxy Model (BCPM) that is jointly sponsored by Sprint, US WEST, and Pacific Bell. The network design embedded in BCPM is technically sound, consistent with accepted engineering standards, and produces a network capable of providing the same high quality service in rural as well as in urban areas. Sprint urges the Commission to adopt the BCPM as the platform model for determining USF funding. Further, Sprint believes that although there remain several open issues (such as switching costs), these issues can be fully addressed and resolved prior to January 1, 1998, and that the Commission should focus its resources on resolving these issues rather than developing some alternative interim plan.

Following is Sprint's proposal for accomplishing that objective. First, Sprint recognizes and indeed shares the concerns expressed relative to the size of the USF fund implied by the BCPM results, using the default input values in that model. Based on its review of the criticisms of the BCPM inputs, a review of Sprint Local Telecom Division costs for some cost inputs, and input changes suggested by others (in particular, the Joint

Board Staff), Sprint has modified the inputs to BCPM to produce USF cost results that represent, on balance, a reasonable starting point for a proxy based USF fund.¹

Second, Sprint proposes a workplan to resolve what it believes to be the major outstanding issues relative to the BCPM model and model inputs, with a view to reaching final resolution of these issues prior to January 1, 1998.

This proposal, and the model input changes described below, represent the position of Sprint Corporation only, and not that of the other BCPM model sponsors.

SPRINT PROPOSED BCPM INPUT VALUES

The default input values in BCPM were derived from a survey of large LECs. The objective of the survey was to develop input values more representative of nationwide average costs than would be the case if the cosponsors of BCPM relied only on their own cost data. The BCPM results based on those default inputs, in particular the \$23 billion USF at a \$20 benchmark rate, have raised serious concerns as to the validity of those inputs.

Responding to these concerns, Sprint has independently reassessed the default input values, and has identified a number of changes that fall, in its view, within the range of reasonableness and would provide a reasonable basis for a national USF fund. Some of these input changes represent substitution of Sprint LTD costs for the default values in the

¹ Although Sprint believes the revised input changes are reasonable for USF purposes, it does not concede that all of the revisions are appropriate for determining the costs of unbundled elements. In particular, Sprint's experienced switch costs are considerably greater than the revised inputs, and Sprint retains the right to determine its unbundled switching rates based on Sprint specific costs.

model (for example, cable costs and Digital Loop Carrier(DLC) costs). Others represent input values suggested by the Joint Board Staff (for example, depreciation lives and structure sharing). Finally, Sprint recognizes that there is a fundamental disagreement on the level of switching costs, and that this issue can only be resolved by Commission access to and validation of cost data that is proprietary to switch vendors. Pending resolution of this matter, Sprint proposes that the lower switch costs incorporated in the BCM2 model be used. Although the current BCPM values more closely approximate Sprint's current costs of switching, Sprint believes that it would be appropriate for the Commission to use the more conservative input costs until it has concluded its own investigation of this issue.

Following is a summary of the input changes made by Sprint. A copy of the revised BCPM input tables is attached.

- Cost of Capital has been revised to the Commission's currently prescribed
 11.25%.²
- 2. Depreciation lives for switching, circuit equipment, and copper plant have been lengthened to 12, 10, and 18 years, respectively.²
- 3. Structure sharing has been revised to assign 66% of manholes and buried structure placement costs, and 50% of poles, to the incumbent LEC.
- 4. Copper and fiber material costs have been reduced by 20%. Based on a review of its own costs, Sprint has found that its costs are approximately 10% below

² Sprint recognizes that the cost of capital and depreciation life adjustments arguably violate the criteria that the model should represent the forward looking economic costs of a new entrant. However, given that the vast preponderance of USF will initially flow to incumbent LECs, Sprint believes it would not be inappropriate for the Commission to relax this criteria for the initial implementation of the new USF, and use instead inputs that more closely approximate regulatory prescribed capital costs and depreciation lives for ILECs.

the default costs in the model. In addition, Sprint believes a further adjustment of 10% is appropriate to reflect that the RBOCs and GTE should experience even lower costs due to the volume of their purchases.

5. Sprint likewise adjusted the costs for DLCs, Feeder Distribution Interfaces, and manholes consistent with Sprint's internal costs for these items.

REVISED BCPM RESULTS

The input modifications described above produce a nationwide average monthly cost per access line of \$29.14. At the \$20 benchmark level, this produces a USF fund of \$15.1 billion (a detailed output report is attached). Of this amount, approximately \$600 million is the USF costs for single line businesses, and \$14.5 billion for residential lines. USF costs at the \$30 benchmark are \$8.3 billion.

PROPOSED WORKPLAN FOR A JANUARY 1, 1998 IMPLEMENTATION DATE

The BCPM model input changes described above represent a reasonable starting point for initiating a proxy-based USF on January 1, 1998. However, Sprint believes that further refinements can and should be made prior to implementation. Although there are literally thousands of inputs to the BCPM, Sprint believes that the vast majority of those inputs are reasonable, and that efforts at further refining them will not materially affect the costs produced by the model. Rather, the Commission should focus its review and validation efforts on the following areas which constitute the major areas of concern expressed by independent parties and where changes in those inputs could materially affect the costs produced by the model.

Again, Sprint urges the Commission to adopt the BCPM as the basic platform for determining USF costs. To continue to simultaneously analyze fundamentally different models under various input assumptions will needlessly complicate the task of developing and implementing a USF fund by January 1, 1998. From a purely technical, network design standpoint, the BCPM is clearly superior to the other models that have been placed on the record. Sprint believes that the BCPM is not only fundamentally sound, but is also the only model that conforms to the criteria set forth by the Joint Board. In addition, the BCPM provides the ability to change the default inputs, so that the Commission is in no way constrained to the default input values in the model. Finally, the BCPM model itself is open and unprotected, making it not only easy to audit, but also providing the capability to modify any of the formulas or algorithms³. Thus, the Commission has total control over both the model and the model inputs, and can revise these where it finds it appropriate to do so.

Using the BCPM as a platform, the major issues that need to be addressed are the following:

1. Switching costs. As discussed above, there exists a fundamental disagreement concerning the costs of switching. This dispute is grounded in the unavailability of public data on the prices paid by LECs for switching equipment. This price data is proprietary to the switch vendors, and LECs are not permitted to divulge this data publicly. Sprint believes that the only means of resolving this

³ In this regard, Sprint believes it would be appropriate to modify the BCPM's treatment of operating expenses. The model currently assigns all operating expenses on a per access line basis. Sprint believes that allocating investment related expenses on investment would better reflect cost causation, and that the BCPM should be modified to reflect this method.

- issue is for the Commission to review switch vendor proprietary data under protective cover, and use the results of that review to develop average or generic switch cost functions (masking the prices of individual switch vendors) for use in determining USF costs.
- 2. Rate of return, depreciation, and structure sharing. Outside of switching costs (discussed above) and network design for rural areas (discussed below), these three inputs are the predominant drivers of the cost differences between the Hatfield and BCPM models, and therefore warrant the greatest scrutiny by the Commission.
- 3. Low density areas. There are two issues relative to low density or rural areas that require further attention. First is the quality of service. The BCPM designs a network that provides the same level of service quality in rural areas as in urban areas. In contrast, the Hatfield model incorporates a network design that produces a systematically lower quality of service in rural areas, and, indeed, in some instances a network that simply would not work. Fundamentally, however, the appropriate quality of service in rural areas is a policy decision that must be made by the Commission and the Joint Board.
 Second, the BCPM assumes a uniform distribution of customers in rural areas. In those areas where this is not the case (for example, if customers are clustered in small towns rather than uniformly distributed over the countryside)

sprint is continuing to work on this issue by utilizing smaller geographic areas (such as Census Blocks) in order to better identify actual customer locations and thereby better estimate the costs of providing facilities to serve those customers. Although Sprint believes that improvements in determining the costs in very rural areas can be accomplished before January 1, 1998, it would also support a years delay in the adoption of a proxy based USF for small companies to ensure that they are not adversely impacted by the adoption of a

CONCLUSION

model that does not adequately reflect the costs of service in rural areas.

It is critical that the Commission continue to pursue the implementation of a proxy based USF fund, at least for large LECs, effective January 1, 1998. It is equally critical that the Commission adopt a model and model inputs that not only reflect a network design capable of producing a high quality of service, but also incorporate a realistic assessment of the costs of building such a network. The BCPM model, with the input changes suggested by Sprint, meets these criteria. Sprint urges the Commission to adopt the BCPM platform and the Sprint input changes as a basis for implementing a proxy-based USF plan.

⁴ The Hatfield model doesn't resolve this issue. Although it attempts to recognize clustering, it not only presumes (erroneously) that all rural areas are clustered, but also "fixes" the problem by simply disregarding all customers living outside of the clusters, thereby significantly understating the costs in rural areas.

ATTACHMENT

Sprint Revised Input Values

Material Costs

0.11-61-		Filin	g Copper Distribut	Ļ		un	Copper Distribution	on C			
Cable Size	Cost Underground		Cost Buried		Cost Aerial	Ľ	Cost Underground		Cost Buried		Cost Aerial
3600	\$ 33.30	<u> </u>	30.20	\$	34.01	5	19.98	S	18.12	\$	20.41
3000	\$ 28.21	\$	29.19	\$	33.36	\$	19.25	\$	17.51	\$	20.02
2400	\$ 23.02	\$	25.79	S	26.26	S	13.97	\$	15.47	S	15.76
2100	\$ 19.50	\$	22.56	\$	20.88	\$	13.60	\$	14.46	\$	12.53
1800	\$ 17.55	\$	20.46	\$	19.28	\$	12.39	\$	13.58	S	11.57
1200	\$ 12.07	\$	13.20	\$	12.78	S	8.12	\$	9.25	\$	7.67
900	\$ 9.40	S	10.70	\$	9.86	\$	6.77	\$	7.26	S	6.26
600	\$ 7.52	\$	7.27	\$	7.21	\$	5.17	S	5.78	S	4.69
400	\$ 6.55	\$	5.67	\$	5.58	\$	4.01	\$	4.60	\$	3.60
300	\$ 4.42	S	4.38	\$	4.88	s	3.59	\$	4.06	\$	3.20
200	\$ 3.60	\$	3.49	\$	3.84	\$	3.16	\$	3.62	\$	2.81
100	\$ 2.65	\$	2.52	\$	2.99	\$	2.49	\$	2.99	\$	2.14
50	\$ 2.42	S	2.16	\$	2.59	\$	2.21	\$	2.77	\$	2.14
25	\$ 1.51	\$	1.93	\$	2.50	\$	2.11	\$	2.67	\$	2.01
18	\$ 1.32	S	Į.75	\$	2.18	\$	0.79	\$	1.05	\$	1.31
12	\$ 1.16	S	1.28	\$	1.92	\$	0.70	\$	2.68	\$	2.00

		FCC	Fil	ing CopperFeeder	Cost	<u>t</u>		Sprin	t R	un CopperFeeder (Cos	1
FeederCableSize	•	Cost Underground		Cost Buried		Cost Aerial		Cost Underground		Cost Buried		Cost Aerial
4200	\$	35.60	\$	33.16	S	37.18	\$	21.36	\$	19.90	\$	22.31
3600	S	33.30	\$	30.20	\$	34.01	\$	19.98	\$	18.12	\$	20.41
3000	\$	28.21	S	29.19	\$	33.36	S	19.25	\$	17.51	\$	20.02
2400	\$	21.50	\$	26.79	\$	26,26	\$	13.97	\$	15.47	\$	15.76
2100	\$	19.49	\$	22.60	\$	20.88	\$	13.60	\$	14.46	\$	12.53
1800	\$	17.38	\$	20.46	\$	19.28	\$	12.39	\$	13.58	\$	11.57
1200	\$	11.95	S	13.20	\$	12.78	\$	8.12	\$	9.25	\$	7.67
900	\$	9.98	\$	10.70	\$	9.86	\$	6.77	\$	7.26	\$	6.26
600	\$	7.52	\$	7.27	\$	7.21	\$	5.17	\$	5.78	\$	4.69
400	\$	6.55	\$	5.67	\$	5.58	\$	4.01	\$	4.60	\$	3.60
300	\$	4.42	S	4.38	\$	4.88	\$	3.59	\$	4.06	\$	3.20
200	\$	3.60	s	3,49	\$	3.84	\$	3.16	\$	3.62	S	2.81
100	\$	2.65	\$	2.52	S	2.99	\$	2.49	\$	2.99	\$	2.14
50	\$	1.19	\$	2.16	\$	2.59	\$	2.21	\$	2.77	\$	2.14
25	\$	1.00	\$	1,93	\$	2.50	\$	2.11	\$	2.67	\$	2.01

Material Costs

							Γ							
			FC	C Filing Fiber Cos	t		L	s	pri	nt Run Fiber Cost				
FiberCableSize Cost Underground Cost Buried Cost Aerial								Cost Underground Cost Buried Cost Aer						
288	\$	11.50	\$	12.79	\$	12,02	3	6.56	S	7.67	\$	7.21		
144	\$	10.30	S	9.96	\$	9.85	3	5.08	\$	5.97	5	5.91		
96	\$	7.40	\$	7.43	\$	7.19	S	4.01	\$	4.46	S	4.31		
72	\$	6.25	\$	6.00	\$	6.75	\$	3.54	\$	3.60	S	4.05		
60	\$	5.50	\$	5.17	S	6.02	S	3.28	S	3.10	\$	3.61		
48	\$	4.75	\$	4.95	\$	5.27	\$	2.93	\$	2.97	S	3.16		
36	\$	4.15	\$	4.01	\$	4.67	\$	2.62	\$	2.40	\$	2.80		
24	\$	3.75	\$	3.93	S	3.45	\$	2.32	\$	2.36	\$	2.07		
18	\$	3.48	\$	3.25	\$	3.26	\$	2.23	\$	1.95	S	1.96		
12	\$	3.09	\$	2.75	\$	3.04	\$	1.97	\$	1.65	\$	1.82		

Feeder Distribution	n Interface Cost Tabl	e
Size	FCC FilingTotal Cost	Sprint Run Total Cost
0	\$ 407.00	\$ 407.00
26	\$ 1,885.00	\$ 1,885.00
51	\$ 2,120.00	\$ 2,120.00
101	\$ 2,355.00	\$ 2,355.00
151	\$ 2,590.00	\$ 2,590.00
201	\$ 5,509.49	\$ 4,423.00
301	\$ 6,848.35	\$ 5,182.00
451	\$ 7,586.00	\$ 5,974.00
601	\$ 8,717.30	\$ 7,028.00
901	\$ 11,489.93	\$ 7,507.00
1351	\$ 11,712.81	\$ 9,038.00
1801	\$ 17,222.30	\$ 13,461.00
2101	\$ 18,561.15	\$ 14,220.00
2251	\$ 19,298.81	\$ 15,012.00
2401	\$ 20,430.11	\$ 16,066.00
2701	\$ 23,202.74	\$ 16,545.00
3150	\$ 23,425.62	\$ 18,076.00

Digital Carrier Cost Table

	Cost for D	igital Loop Carri						
Dic Fiber Size	FCC Fi	ling Fixed Cost	FCC Fili Cost	ng Per Line		t Run Fixed Cost	Sprint Run Cost	Per Line
0	\$	38,867.00	\$	92.81	\$	10,395.00	S	250.00
49	\$	53,577.00	S	92.81	\$	11,475.00	\$	250.00
121	\$	84,976.00	\$	92.81	\$	14,175.00	\$	250.00
241	\$	92,147.00	\$	92.81	\$	92,147.00	\$	92.81
673	\$	125,120.85	S	92.81	S	125,120.85	\$	92.81
1335	\$	217,267.85	S	92.81	S	217,267.85	S	92.81

CO Switch Cost Table

Company Size	FCC Filing Fixed/Startup \$	FCC Filing Per Line	FCC Filing Power and Common Equipment %	Fcc Fillng Telco Install and Engineering %	F	Sprint Run Fixed/Startup \$	Sprint Run Per Line \$	Sprint Run Power and Common Equipment %	Sprint RunTelco Install and Engineering %
S	\$ 261,871.00	\$ 225.00	6.82%	5.77%	S	150,000.00	\$ 110.00	6.82%	5.77%
M	\$ 261,871.00	\$ 225.00	6.82%	5.77%	S	150,000.00	\$ 110.00	6.82%	5.77%
L	\$ 261,871.00	\$ 225.00	6.82%	5.77%	S	150,000.00	\$ 110.00	6.82%	5.77%

Conduit Manhole Table

FCC Filing

Sprint Run

% Assigned	Cost of in	stalle	d facility assigned	telephone	% Assigned	Cost of installed facility assigned telephone								
Telephone	Normal	Soft Rock		Hard Rock	Telephone		Normal		Soft Rock	Hard Rock				
75%	\$ 1,008.00	\$	1,158.00	\$1,308.00	66%	\$	887.04	S	1,019.04	\$1,151.04				
90%	\$ 3,404.93	\$	3,764.93	\$4,124.93	66%	\$	2,496.95	\$	2,760.95	\$3,024.95				
80%	\$ 4,512.00	S	4,832.00	\$5,152.00	66%	\$	3,722.40	S	3,986.40	\$4,250.40				
80%	\$ 2,640.00	\$	2,800.00	\$2,960.00	66%	\$	2,178.00	\$	2,310.00	\$2,442.00				
100%	\$ 0.83		NA	NA	100%	\$	0.83		NA	NA				

Under Ground Structure

Dane	Group	n.	tA

	Normal	Normal	Normal	Normal	Soft Rock	Soft Rock	Soft Rock	Soft Rock	Hard Rock	Hard Rock	Hard Rock	Hard Rock
	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution
	FCC Filing %	Sprint Run %										
	Assigned											
Conduit Installation	Telephone											
Trench & Backfill	100.00%	66.00%	100.00%	66.00%	100.00%	66.00%	100.00%	66,00%	100.00%	66.00%	100.00%	66.00%
Rocky Trench	100.00%	66.00%	100.00%	66.00%	100.00%	66,00%	100.00%	66.00%	100.00%	66.00%	100.00%	66.00%
Backhoe Trench	100.00%	66.00%	100,00%	66.00%	100.00%	66.00%	100.00%	66.00%	100.00%	66.00%	100.00%	66.00%
Hand Dig Trench	100.00%	66,00%	100.00%	66.00%	100,00%	66.00%	100.00%	66.00%	100,00%	66.00%	100.00%	66,00%
Boring	100.00%	66.00%	100.00%	66.00%	100.00%	66,00%	100.00%	66.00%	100.00%	66.00%	100,00%	66.00%
Cut & Restore Asphalt	100.00%	66.00%	100.00%	66.00%	100.00%	66.00%	100.00%	66,00%	100.00%	66.00%	100.00%	66.00%
Cut & Restore Concrete	100.00%	66,00%	100.00%	66.00%	100.00%	66.00%	100.00%	66.00%	100,00%	66.00%	100.00%	66.00%
Cut & Restore Sod	100,00%	66.00%	100.00%	66.00%	100,00%	66.00%	100.00%	66,00%	100.00%	66.00%	100.00%	66.00%

Density Group 11-50

	Normal	Normal	Normal	Normal	Soft Rock	Soft Rock	Soft Rock	Soft Rock	Hard Rock	Hard Rock	Hard Rock	Hard Rock
	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution
	FCC Filing %	Sprint Run %										
]	Assigned											
Conduit Installation	Telephone											
Trench & Backfill	97.50%	66.00%	95.00%	66.00%	97.50%	66.00%	95.00%	66.00%	97.50%	66.00%	95.00%	
Rocky Trench	97.50%	66.00%	95.00%	66.00%	97.50%	66.00%	95.00%	66.00%	97.50%	66.00%	95.00%	66.00%
Backhoe Trench	97.50%	66.00%	95.00%	66.00%	97.50%	66.00%	95.00%	66.00%	97.50%	66.00%	95.00%	66,00%
Hand Dig Trench	97.50%	66,00%	95.00%	66,00%	97.50%	66.00%	95,00%	66.00%	97.50%	66.00%	95.00%	66.00%
Boring	97.50%	66,00%	95.00%	66.00%	97.50%	66.00%	95.00%	66,00%	97.50%	66,00%	95.00%	66.00%
Cut & Restore Asphalt	97.50%	66.00%	95.00%	66.00%	97.50%	66.00%	95.00%	66.00%	97.50%	66.00%	95.00%	66.00%
Cut & Restore Concrete	97.50%	66,00%	95.00%	66.00%	97.50%	66.00%	95.00%	66.00%	97.50%	66,00%	95.00%	
Cut & Restore Sod	97.50%	66.00%	95.00%	66.00%	97.50%	66,00%	95.00%	66,00%	97.50%	66,00%	95.00%	66.00%

Density Group 51-150

Density Group 31-130												
	Normal	Normal	Normal	Normal	Soft Rock	Soft Rock	Soft Rock	Soft Rock	Hard Rock	Hard Rock	Hard Rock	Hard Rock
	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution
	FCC Filing %	Sprint Run %										
	Assigned											
Conduit Installation	Telephone											
Trench & Backfill	95.00%	66,00%	90.00%	66.00%	95.00%	66.00%	90.00%	66.00%	95,00%	66.00%	90.00%	66,00%
Rocky Trench	95.00%	66,00%	90,00%	66,00%	95.00%	66,00%	90.00%	66,00%	95.00%	66.00%	90.00%	66.00%
Backhoe Trench	95.00%	66,00%	90.00%	66.00%	95,00%	66.00%	90,00%	66,00%	95,00%	66,00%	90.00%	66.00%
Hand Dig Trench	95.00%	66.00%	90.00%	66.00%	95,00%	66.00%	90.00%	66.00%	95.00%	66.00%	90.00%	66,00%
Boring	95.00%	66.00%	90,00%	66.00%	95.00%	66.00%	90.00%	66,00%	95.00%	66.00%	90.00%	66.00%
Cut & Restore Asphalt	95.00%	66,00%	90.00%	66.00%	95.00%	66.00%	90.00%	66.00%	95,00%	66.00%	90.00%	66,00%
Cut & Restore Concrete	95,00%	66,00%	90.00%	66,00%	95.00%	66.00%	90.00%	66.00%	95,00%	66.00%	90.00%	66.00%
Cut & Restore Sod	95.00%	66.00%	90,00%	66.00%	95.00%	66,00%	90.00%	66,00%	95.00%	66,00%	90,00%	66.00%

Density Group 151-500												
	Normal	Normal	Normal	Normal	Soft Rock	Soft Rock	Soft Rock	Soft Rock	Hard Rock	Hard Rock	Hard Rock	Hard Rock
	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution
	FCC Filing %	Sprint Run %										
	Assigned											
Conduit Installation	Telephone											
Trench & Backfill	92.50%	66,00%	80,00%	66.00%	92.50%	66,00%	80.00%	66.00%	92.50%	66.00%	80.00%	66.00%
Rocky Trench	92.50%	66.00%	80,00%	66.00%	92.50%	66,00%	80.00%	66.00%	92.50%	66.00%	80.00%	66.00%
Backhoe Trench	92.50%	66,00%	80.00%	66.00%	92.50%	66,00%	80.00%	66.00%	92.50%	66.00%	80,00%	66.00%
Hand Dig Trench	92.50%	66,00%	80,00%	66.00%	92.50%	66,00%	80.00%	66.00%	92.50%	66.00%	80.00%	66,00%
Boring	92.50%	66.00%	80.00%	66.00%	92.50%	66,00%	80.00%	66.00%	92.50%	66.00%	80.00%	66.00%
Cut & Restore Asphalt	92.50%	66.00%	80,00%	66.00%	92.50%	66.00%	80.00%	66,00%	92.50%	66.00%	80.00%	66.00%
Cut & Restore Concrete	92.50%	66.00%	80.00%	66.00%	92.50%	66.00%	80.00%	66.00%	92.50%	66.00%	80.00%	66.00%
Cut & Restore Sod	92.50%	66.00%	80.00%	66.00%	92.50%	66.00%	80.00%	66.00%	92.50%	66.00%	80.00%	66.00%
D												
Density Group 501-2000	N	Ata	Ma	M	0-8-5	0-00-1	0.00	0-00-1		Head Beat	Hand Dack	Hard Rock
	Normal	Normal	Normal	Normal	Soft Rock	Soft Rock	Soft Rock	Soft Rock	Hard Rock	Hard Rock	Hard Rock	Distribution
	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	
	FCC Filing %	Sprint Run %										
	Assigned											
Conduit Installation	Telephone											
Trench & Backfill	90.00%	66,00%	80,00%	66.00%	90.00%	66,00%	80.00%	66.00%	90.00%	66.00%	80.00%	66.00%
Rocky Trench	90.00%	66.00%	80,00%	66.00%	90.00%	66,00%	80.00%	66.00%	90.00%	66.00%	80.00%	66.00%
Backhoe Trench	90.00%	66.00%	80.00%	66.00%	90.00%	66.00%	80.00%	66.00%	90.00%	66.00%	80.00%	66.00%
Hand Dig Trench	90.00%	66.00%	80,00%	66.00%	90,00%	66,00%	80.00%	66.00%	90.00%	66.00%	80.00%	66.00%
Boring	90.00%	66.00%	80,00%	66.00%	90.00%	66.00%	80.00%	66.00%	90.00%	66.00%	80.00%	66,00%
Cut & Restore Asphalt	90.00%	66.00%	80.00%	66.00%	90.00%	66.00%	80.00%	66.00%	90.00%	66.00%	80,00%	66.00%
Cut & Restore Concrete	90.00%	66.00%	80,00%	66.00%	90.00%	66.00%	80.00%	66.00%	90.00%	66.00%	80.00%	66.00%
Cut & Restore Sod	90.00%	66.00%	80,00%	66.00%	90.00%	66.00%	80.00%	66,00%	90,00%	66.00%	80.00%	66.00%
Density Group > 2001												
Density Group's 2001	Normal	Normal	Normal	Normai	Soft Rock	Soft Rock	Soft Rock	Soft Rock	Hard Rock	Hard Rock	Hard Rock	Hard Rock
	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution
	FCC Filing %	Sprint Run %										
	Assigned											
Conduit Installation	Telephone											
Trench & Backfill	85.00%	66,00%	80,00%	66.00%	85.00%	66.00%	80,00%	66,00%	85,00%	66.00%	80.00%	66,00%
Rocky Trench	85.00%	66,00%	80.00%	66.00%	85.00%	66.00%	80,00%	66.00%	85,00%	66,00%	80,00%	66.00%
Backhoe Trench	85.00%	66,00%	80.00%	66,00%	85.00%	66,00%	80.00%	66,00%	85,00%	66,00%	80.00%	66.00%
Hand Dig Trench	85.00%	66,00%	80.00%	66.00%	85.00%	66.00%	80.00%	66.00%	85,00%	66,00%	80.00%	66,00%
Boring	85.00%	66.00%	80.00%	66.00%	85.00%	66,00%	80.00%	66,00%	85,00%	66,00%	80.00%	66,00%
Cut & Restore Asphalt	85.00%	66.00%	80.00%	66.00%	85.00%	66,00%	80.00%	66.00%	85.00%	66,00%	80,00%	66.00%
Cut & Restore Concrete	85.00%	66.00%	80.00%	66.00%	85,00%	66,00%	80.00%	66.00%	85,00%	66.00%	80,00%	66,00%
Cut & Restore Sod	85.00%	66.00%	80.00%	66,00%	85.00%	66,00%	80.00%	66.00%	85,00%	66.00%	80.00%	66.00%
Cur de restore aud	85.0076	00.0076	80.0076	00,0076	03.00%	50,00%	80.00%	00.00%	0,00%	00,0076	00,0078	00,0076

Buried Structure

Density Group 0-10

	Normal Feeder	Normal Feeder	Normal Distribution	Normal Distribution	Soft Rock Feeder	Soft Rock Feeder	Soft Rock Distribution	Soft Rock Distribution	Hard Rock Feeder	Hard Rock Feeder	Hard Rock Distribution	Hard Rock Distribution
	FCC Filing %	Sprint Run %	FCC Filing %	Sprint Run %	FCC Filing %	Sprint Run %	FCC Filing %	Sprint Run %	FCC Filing %	Sprint Run %	FCC Filing %	Sprint Run %
1	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned
Buried Cable Installation	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone
Plow	100.00%	100.00%	100,00%	100.00%	100.00%	100.00%	100,00%	100,00%	100.00%	100.00%	100.00%	100,00%
Rocky Plow	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100,00%	100.00%	100.00%	100.00%	100.00%
Trench & Backfill	100.00%	66.00%	100.00%	66,00%	100.00%	66.00%	100.00%	66.00%	100.00%	66.00%	100.00%	66.00%
Rocky Trench	100.00%	66.00%	100.00%	66.00%	100.00%	66.00%	100,00%	66,00%	100.00%	66.00%	100.00%	66.00%
Backhoe Trench	100.00%	66.00%	100,00%	66.00%	100.00%	66.00%	100.00%	66.00%	100.00%	66.00%	100.00%	66.00%
Hand Dig Trench	100.00%	66,00%	100.00%	66.00%	100.00%	66,00%	100.00%	66,00%	100.00%	66.00%	100.00%	66.00%
Bore Cable	100.00%	66.00%	100.00%	66.00%	100.00%	66,00%	100.00%	66.00%	100.00%	66.00%	100.00%	66.00%
Push Pipe & Pull Cable	100.00%	66,00%	100.00%	66.00%	100.00%	66.00%	100.00%	66,00%	100.00%	66,00%	100.00%	66.00%
Cut & Restore Asphalt	100.00%	66.00%	100.00%	66,00%	100.00%	66.00%	100.00%	66.00%	100.00%	66.00%	100.00%	66.00%
Cut & Restore Concrete	100,00%	66.00%	100,00%	66.00%	100.00%	66.00%	100.00%	66,00%	100.00%	66.00%	100.00%	66.00%
Cut & Restore Sod	100.00%	66.00%	100.00%	66,00%	100.00%	66,00%	100.00%	66.00%	100.00%	66,00%	100.00%	66.00%

Density Group 11-50

	Normal	Normal	Normal	Normal	Soft Rock	Soft Rock	Soft Rock	Soft Rock	Hard Rock	Hard Rock	Hard Rock	Hard Rock
	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution
	FCC Filing %	Sprint Run %										
	Assigned											
Buried Cable Installation	Telephone											
Plow	100.00%	100.00%	100.00%	100.00%	100,00%	100.00%	_100.00%	100,00%	100,00%	100.00%	100.00%	100,00%
Rocky Plow	100.00%	100,00%	100,00%	100.00%	100.00%	100.00%	100,00%	100,00%	100.00%	100.00%	100.00%	100.00%
Trench & Backfill	97.50%	66.00%	95.00%	66.00%	97.50%	66.00%	95.00%	66.00%	97.50%	66.00%	95.00%	66.00%
Rocky Trench	97.50%	66,00%	95.00%	66.00%	97.50%	66.00%	95.00%	66.00%	97.50%	66.00%	95.00%	66,00%
Backhoe Trench	97.50%	66.00%	95,00%	66.00%	97.50%	66.00%	95.00%	66.00%	97.50%	66.00%	95,00%	66.00%
Hand Dig Trench	97.50%	66.00%	95.00%	66.00%	97.50%	66,00%	95.00%	66.00%	97,50%	66.00%	95,00%	66,00%
Bore Cable	97.50%	66.00%	95.00%	66.00%	97.50%	66,00%	95,00%	66.00%	97.50%	66.00%	95.00%	66.00%
Push Pipe & Pull Cable	97.50%	66.00%	95,00%	66.00%	97.50%	66.00%	95.00%	66.00%	97.50%	66.00%	95,00%	66.00%
Cut & Restore Asphalt	97.50%	66.00%	95,00%	66.00%	97.50%	66.00%	95,00%	66.00%	97.50%	66.00%	95.00%	66.00%
Cut & Restore Concrete	97.50%	66.00%	95.00%	66.00%	97.50%	66,00%	95.00%	66.00%	97,50%	66,00%	95.00%	66,00%
Cut & Restore Sod	97.50%	66,00%	95.00%	66,00%	97.50%	66.00%	95.00%	66.00%	97.50%	66.00%	95.00%	66.00%

	ens	itv	Groun	3 51-1	150
--	-----	-----	-------	--------	-----

	Normal Feeder	Normal Feeder	Normal Distribution	Normal Distribution	Soft Rock Feeder	Soft Rock Feeder	Soft Rock Distribution	Soft Rock Distribution	Hard Rock Feeder	Hard Rock Feeder	Hard Rock Distribution	Hard Rock Distribution
	FCC Filing %	Sprint Run %	FCC Filing %	Sprint Run %	FCC Filing %	Sprint Run %	FCC Filing %	Sprint Run %	FCC Filing %	Sprint Run %	FCC Filing %	Sprint Run %
	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned
Buried Cable Installation	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone
low	100.00%	100.00%	100,00%	100.00%	100.00%	100.00%	100.00%	100,00%	100.00%	100.00%	100.00%	100.00%
locky Plow	100.00%	100.00%	100,00%	100.00%	100.00%	100.00%	100.00%	100,00%	100.00%	100.00%	100.00%	100.00%
rench & Backfill	95.00%	66,00%	90,00%	66.00%	95.00%	66.00%	90.00%	66.00%	95.00%	66.00%	90.00%	66,00%
locky Trench	95,00%	66,00%	90.00%	66.00%	95.00%	66.00%	90.00%	66.00%	95.00%	66,00%	90.00%	66,00%
lackhoe Trench	95.00%	66,00%	90.00%	66.00%	95.00%	66.00%	90.00%	66.00%	95.00%	66.00%	90.00%	66,00%
land Dig Trench	95.00%	66.00%	90.00%	66.00%	95.00%	66,00%	90.00%	66,00%	95.00%	66.00%	90.00%	66,00%
fore Cable	95.00%	66.00%	90.00%	66.00%	95.00%	66.00%	90.00%	66.00%	95.00%	66.00%	90.00%	66.00%
'ush Pipe & Pull Cable	95.00%	66.00%	90,00%	66.00%	95.00%	66,00%	90.00%	66,00%	95,00%	66.00%	90.00%	66,00%
ut & Restore Asphalt	95.00%	66.00%	90.00%	66.00%	95.00%	66,00%	90,00%	66.00%	95.00%	66,00%	90.00%	66,00%
Jut & Restore Concrete	95.00%	66.00%	90.00%	66.00%	95.00%	66.00%	90.00%	66.00%	95.00%	66.00%	90.00%	66.00%
int & Restore Sod	95.00%	66.00%	90.00%	66.00%	95.00%	66,00%	90.00%	66.00%	95.00%	66.00%	90.00%	66,00%

Pensity Group 151-500

•	Normal Feeder	Normal Feeder	Normal Distribution	Normal Distribution	Soft Rock Feeder	Soft Rock Feeder	Soft Rock Distribution	Soft Rock Distribution	Hard Rock Feeder	Hard Rock Feeder	Hard Rock Distribution	Hard Rock Distribution
	FCC Filing %	Sprint Run %	FCC Filing %	Sprint Run %	FCC Filing %	Sprint Run %	FCC Filing %	Sprint Run %	FCC Filing %	Sprint Run %	FCC Filing %	Sprint Run %
	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned	Assigned
Buried Cable Installation	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone	Telephone
How	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100,00%	100.00%
Rocky Plow	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100,00%	100.00%
French & Backfill	92.50%	66,00%	80.00%	66,00%	92,50%	66,00%	80,00%	66,00%	92.50%	66,00%	80,00%	66.00%
Rocky Trench	92.50%	66.00%	80.00%	66.00%	92,50%	66,00%	80.00%	66.00%	92.50%	66,00%	80.00%	66.00%
Backhoe Trench	92.50%	66.00%	80.00%	66.00%	92.50%	66.00%	80.00%	66.00%	92.50%	66.00%	80.00%	66.00%
Hand Dig Trench	92.50%	66.00%	80.00%	66.00%	92,50%	66.00%	80.00%	66.00%	92.50%	66,00%	80.00%	66.00%
Bore Cable	92.50%	66.00%	80.00%	66.00%	92.50%	66.00%	80.00%	66.00%	92.50%	66.00%	80.00%	66.00%
Push Pipe & Pull Cable	92.50%	66.00%	80.00%	66,00%	92.50%	66,00%	80,00%	66.00%	92.50%	66,00%	80,00%	66.00%
Cut & Restore Asphalt	92.50%	66.00%	80.00%	66.00%	92,50%	66.00%	80.00%	66.00%	92.50%	66.00%	80.00%	66.00%
Cut & Restore Concrete	92.50%	66.00%	80.00%	66,00%	92.50%	66,00%	80.00%	66.00%	92.50%	66,00%	80,00%	66.00%
Cut & Restore Sod	92.50%	66.00%	80.00%	66.00%	92.50%	66,00%	80.00%	66.00%	92.50%	66,00%	80.00%	66.00%

ensity	Group	501-2000
--------	-------	----------

	Normal	Normal	Normal	Normal	Soft Rock	Soft Rock	Soft Rock	Soft Rock	Hard Rock	Hard Rock	Hard Rock	Hard Rock
	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution
	FCC Filing %	Sprint Run %										
1	Assigned											
Buried Cable Installation	Telephone											
Plow	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%
Rocky Plow	100.00%	100.00%	. 100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100,00%	100.00%	100.00%
Trench & Backfill	90.00%	66.00%	80.00%	66.00%	90.00%	66.00%	80.00%	66.00%	90.00%	66,00%	80.00%	66.00%
Rocky Trench	90.00%	66.00%	80.00%	66.00%	90.00%	66.00%	80.00%	66.00%	90.00%	66,00%	80,00%	66.00%
Backhoe Trench	90.00%	66.00%	80.00%	66.00%	90.00%	66.00%	80.00%	66,00%	90.00%	66.00%	80.00%	66,00%
Hand Dig Trench	90.00%	66.00%	80,00%	66.00%	90.00%	66.00%	80.00%	66.00%	90,00%	66,00%	80.00%	66.00%
Bore Cable	90.00%	66.00%	80.00%	66.00%	90,00%	66,00%	80.00%	66.00%	90.00%	66,00%	80.00%	66.00%
Push Pipe & Pull Cable	90.00%	66.00%	80.00%	66.00%	90.00%	66.00%	80.00%	66.00%	90.00%	66,00%	80.00%	66,00%
Cut & Restore Asphalt	90.00%	66.00%	80.00%	66.00%	90.00%	66.00%	80.00%	66.00%	90.00%	66,00%	80.00%	66.00%
Cut & Restore Concrete	90.00%	66.00%	80.00%	66.00%	90,00%	66.00%	80.00%	66.00%	90.00%	66,00%	80.00%	66.00%
Cut & Restore Sod	90.00%	66.00%	80.00%	66.00%	90.00%	66.00%	80.00%	66.00%	90.00%	66.00%	80.00%	66.00%

Density Group > 2001

	Normal	Normal	Normal	Normal	Soft Rock	Soft Rock	Soft Rock	Soft Rock	Hard Rock	Hard Rock	Hard Rock	Hard Rock
	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution	Feeder	Feeder	Distribution	Distribution
	FCC Filing %	Sprint Run %										
	Assigned											
Buried Cable Installation	Telephone											
Plow	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100,00%	100.00%	100,00%	100.00%	100.00%
Rocky Plow	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100.00%	100,00%	100.00%	100.00%
Trench & Backfill	85.00%	66.00%	80.00%	66.00%	85.00%	66.00%	80.00%	66.00%	85.00%	66,00%	80.00%	66.00%
Rocky Trench	85.00%	66.00%	80.00%	66.00%	85.00%	66.00%	80.00%	66.00%	85.00%	66,00%	80.00%	66.00%
Backhoe Trench	85.00%	66,00%	80.00%	66.00%	85.00%	66.00%	80,00%	66,00%	85.00%	66,00%	80.00%	66,00%
Hand Dig Trench	85.00%	66.00%	80.00%	66.00%	85.00%	66.00%	80.00%	66.00%	85.00%	66,00%	80.00%	66.00%
Bore Cable	85.00%	66,00%	80,00%	66.00%	85.00%	66.00%	80.00%	66.00%	85,00%	66,00%	80.00%	66.00%
Push Pipe & Pull Cable	85.00%	66.00%	80.00%	66.00%	85.00%	66,00%	80.00%	66.00%	85.00%	66.00%	80.00%	66,00%
Cut & Restore Asphalt	85.00%	66.00%	80.00%	66.00%	85.00%	66.00%	80.00%	66.00%	85.00%	66.00%	80.00%	66.00%
Cut & Restore Concrete	85.00%	66.00%	80.00%	66.00%	85.00%	66.00%	80.00%	66.00%	85.00%	66.00%	80.00%	66.00%
Cut & Restore Sod	85.00%	66.00%	80.00%	66.00%	85.00%	66.00%	80.00%	66.00%	85.00%	66.00%	80,00%	66.00%

Cost - Expense

Financial Data	FCC Filing	Sprint Run
Return on Equity	13.1%	12.9%
Debt Rate	7.8%	7.8%
Debt Ratio	32.8%	32.8%
Discount Rate	7.8%	7.8%
Return on Capital	11.4%	11.25%

Account	FCC Filing Economic Life (years)	Sprint Run Economic Life (years)
Switching	10	12
Circuit/DLC	8.5	10
Aerial Copper	12.5	18
Underground Copper	11.5	18
Buried Copper	14	18

ATTACHMENT

BCPM National Results Using Sprint Input Values

Benchmark Cost Proxy Model Results

Key Elements

National Multiple States [50]

Analysis	Total	Per Line
CBG Lines Served	163,226,155	
Average Distribution Length	475,057,101,947	2,910
Average Feeder Length	2,344,339,961,299	14,363
Average Loop Length	2,819,397,063,247	17,273
Distribution Investment	\$ 112,471,958,816	\$ 689
Feeder Investment	\$ 42,158,659,480	\$ 258
Loop Investment (Uncapped)	\$ 154,630,618,297	\$ 947
Loop Investment (Capped)	\$ 153,978,156,753	\$ 943

Plant Type	C	Capped Annual Investment	Percentage	-	nual Per Line vestment
Motor Vehicle	\$	1,285,867,387	0.70%	\$	7.88
Special Purpose Vehicle	\$	1,740,010	0.00%	\$	0.01
Garage Work	\$	55,680,320	0.03%	\$	0.34
Other Work	\$	1,090,986,267	0.59%	\$	6.68
Furniture	\$	405,422,329	0.22%	\$	2.48
Office	\$	1,219,747,007	0.66%	\$	7.47
General Purpose Computers	\$	5,159,129,636	2.79%	\$	31.61
Total Support Investment	\$	9,218,572,956	4.98%	\$	56.48
Land	\$	234,536,891	0.13%	\$	1.44
Building	\$	1,479,386,557	0.80%	\$	9.06
Switching Equipment	\$	19,462,027,480	10.52%	\$	119.23
Circuit Equipment	\$	25,805,685,953	13.95%	\$	158.10
Buried Cable	\$	58,980,732,665	31.89%	\$	361.34
Aerial Cable	\$	17,835,497,263	9.64%	\$	109.27
Underground Cable	\$	21,124,164,088	11.42%	\$	129.42
Pole Investment	\$	11,158,475,141	6.03%	\$	68.36
Conduit Investment	\$	19,634,416,951	10.62%	\$	120.29
Total Plant Investment	\$	175,714,922,988	95.02%	\$	1,076.51
Total Investment	\$	184,933,495,943	100.00%	\$	1,132.99

Assumptions:

SPRINTDISCOUNTBASE.CSV, CapcostSprintDiscount.inf

USF with Sprint Discounted Cable Prices (0% discount applied)

Benchmark Cost Proxy Model Results

Key Elements

National Multiple States [50]

Ermana Assault	Capped Annual		Percentage	Monthly Per Line Cost	
Expense Account		Expense	rercentage	Li	ne Cost
Plant Specific Expenses	•	001 040 045	0.04~	•	0.15
Network Support	\$	291,848,365	0.84%	•	0.15
General Support	\$	2,350,456,631	6.80%		1.20
COE Switch	\$	665,962,712	1.93%		0.34
Operator Systems	\$	17,628,425	0.05%	\$	0.01
COE Transmission	\$	452,462,901	1.31%	\$	0.23
Information IOT	\$	131,233,829	0.38%	\$	0.07
Cable & Wire	\$	5,404,091,537	15.65%	\$	2.76_
Total Plant Specific Expenses	\$	9,313,684,399	26.96%	\$	4.76
Plant Non-Specific Expenses					
Other PP&E	\$	58,761,416	0.17%	\$	0.03
Network Operations	\$	2,609,006,860	7.55%	\$	1.33
Depreciation/Amort	\$	12,321,299,776	35.67%	\$	6.29
Marketing	\$	693,384,706	2.01%	\$	0.35
Customer Opr Service	\$	4,740,087,539	13.72%	\$	2.42
Executive & Planning	\$	268,343,799	0.78%	\$	0.14
General & Administration	\$	4,203,399,941	12.17%	\$	2.15
Prov Uncollectibles	\$	332,981,356	0.96%	\$	0.17
Total Plant Non-Specific Expenses	\$	25,227,265,393	73.04%	\$	12.88
Total Operating Expense	\$	34,540,949,792	100.00%		17.63
Federal and State Taxes	\$	7,947,312,077		\$	4.06
Return On Investment	_\$	14,586,006,291		\$	7.45
Monthly Cost per Line	\$	57,074,268,159		\$	29.14
Gross Receipts Tax ¹	\$	2,316,229,405		\$	1.18

Assumptions:

SPRINTDISCOUNTBASE.CSV, CapcostSprintDiscount.inf

BCPMSprint.xls

USF with Sprint Discounted Cable Prices (0% discount applied)

¹ Application varies so much on a state by state basis, it is not included in the Monthly Cost.