

Pete Sywenki

Director, Federal Regulatory Relations

Law & External Affairs

1850 M Street, XW, Suite 1100 Washington, DC 20036 Voice 202 828 7452 Fax 202 296 3469 pete.n.sywenki@mail.sprint.com

EX PARTE OR LATE FILED

EX PARTE

April 21, 1998

Ms. Magalie Roman Salas Secretary - Federal Communications Commission 1919 M Street, N.W. Room 222 Washington, D.C. 20554

CC Docket Nos. 96-45 and 97-160₁

RE:

RECEIVE

FEDERAL COMMUNICATIONS COMMISSION OFFICE OF THE SECRETARY

Dear Ms. Salas,

On April 20, 1998, Jim Sichter, Brian Staihr, and Pete Sywenki of Sprint, Whit Jordan of BellSouth, and Glen Brown of USWEST met with Jim Schlichting, Brad Wimmer, Don Stockdale, and Craig Brown of the Common Carrier Bureau with regard to the above referenced dockets. In this meeting, we discussed the status of the cost proxy model platforms currently under the FCC's consideration for use in determining universal service funding for high cost areas. The attached information was discussed in the meeting. These attached materials illustrate the methodology by which customer locations are converted into serving areas for use in the HAI model and point out the way in which this approach significantly understates required distribution facilities.

Included in these materials are estimated distances (lengths) between customer location points within specific clusters. The calculation of these distances was developed by Sprint staff during an on-site review of PNR geo-coded data at PNR Associates (the vendor used by HAI for customer location points and clustering). This review was arranged in response to Sprint's requests during recent Nevada PUC costing proceedings. The information provided during our meeting did not include any actual customer locations or any other information proprietary to PNR. During the meeting, we discussed the continued closed treatment of the HAI clustering information and the need for the Commission to require a full disclosure, to all interested parties, all of the data, algorithms, and other relevant data used by HAI to calculate distribution plant lengths and investment costs. Only a full review would provide for a quantification of the magnitude of the systematic understatement of required distribution facilities in the HAI model that is demonstrated in the attached findings which are based on only the limited review that has been afforded to date.

The original and three copies of this notice are being submitted to the Secretary of the FCC in accordance with Section 1.1206(a)(1) of the Commission's rules. If there are any questions, please call.

Sincerely,
M. Symul.


Pete Sywenki

Attachments


cc: Jim Schlichting

Hatfield's Polygons Converted to Rectangles


The Hatfield 5.0a Model groups a set of "actual" customer points into a *cluster*, according to a set of aggregation rules.




We have determined that the *minimum spanning tree* for these points – the mathematically shortest connection possible for these points – is 5.88 miles.




When Hatfield has determined the set of points that constitute a cluster, it logically draws a *convex hull* around those points, and determines its area.




Hatfield then logically constructs a minimum bounding rectangle – oriented north-south-east-west – that exactly bounds the cluster's points. Hatfield then determines the aspect ratio of that rectangle (that is, the ratio of the rectangle's height to its width) ... in this case, 0.8.



Hatfield then constructs a *rectangle* with the above aspect ratio; the *size* of that rectangle is determined, of course, by its *area* ... and that area is set to be the *area of the convex hull* ... in this case, 3.07 square miles.




Hatfield then constructs *lots* within this constructed rectangle. Each lot is twice as high as it is wide.



A branch cable is then constructed, and 150 ft. drops connect to the customers.

Cabling to Serve Customers

Branch Cable Length = 6177 ft. 10 Drops, each at 150 ft.



Total Cable Length = 7677 ft. = 1.45 mi.


Less than 1/4 of the Minimum Spanning Tree length!

But note how closely the customers are squeezed toward the branch cable. The arrangement is unrealistic, both from the standpoint of cable length *and* from the standpoint of area served.

Customer Area Served

Height = 300 ft.

Width = 106 + 6177 + 106 ft. = 6389 ft.



Area Served = 1,916,700 sq. ft. = 0.0688 sq. mi.

But Actual Cluster Area = 3.07 sq. mi.

Area Modeled is 1/44 of Cluster Area

So, HOW BAD CAN THIS BE?

To what extent does the combined effect of:

- 1) converting the polygon into a rectangle (with identical area) and
- 2) building cable only to the point where the perimeter lots start
- 3) assuming all customers have drops 150 feet or less

cause the model to UNDERSTATE the amount of cable needed to transverse the ACTUAL distances between customers?

The following table shows a sample of several individual clusters (not wire centers) in Nevada (Nevada Bell territory).

The table gives an example of the amount of cable needed to reach all actual customer locations in the cluster. The locations do NOT include any outlier locations. The distance reported is only the distance between points that reside in the main clusters.

This length represents an approximation of the amount of distribution that the Hatfield Model (or any proxy model) should build in the course of laying out the network and determining the associated cost.

The table also shows the amount of actual distribution the Hatfield Model builds to each respective cluster (again, excluding outlier points).

Cluster Number	Absolute Minimum	Total Amount of
	Distance Between	Distribution Cable Built
	Cluster Points (in feet)	by Hatfield Model (in
		feet)
CHBTNV11.C003	23,500	7,900
IMLYNV12.C022	29,000	2,210
UPMDNVXF.C005	29,000	836
IMLYNV12.C015	38,000	2,089
DYTNNV11.C004	21,000	1,494
EMPRNV11.C004	21,500	5,093
EMPRNV11.C003	24,500	0

WHAT DOES THIS EVIDENCE EXPLAIN?

CONCLUSION #1: The Hatfield Sponsors' claim the placing surrogate points on the perimeters of CBs is a conservative approach (causing the model to overstate customer dispersion and therefore overstate required feet of plant) is completely false.

FACT: When points are placed in an (approximately) straight line, the area of the resulting polygon is miniscule and the converted rectangle with identical area distorts (understates) actual customer dispersion immensely.

CONCLUSION #2: This phenomenon has nothing to do with geocoding.

FACT: The understatement of plant does not depend on points being actual or surrogate. If a cluster is made up of 100% actual geocoded points and those points happen to be stretched out in a semi-linear fashion (i.e. along a road where geocoding places points), the same distortion will take place.

CONCLUSION #3: This also explains the significant differences in route mileage produced by the BCPM and the Hatfield Model for the same wire centers.

FACT: In many cases the BCPM estimates 10 times more distribution cable for a given wire center than the Hatfield Model does. Looking at only four clusters in the Imlay, NV wire center, we produce the same table:

Wire Center	Absolute Minimum	Total Amount of
	Distance Between	Distribution Cable Built
	Cluster Points (in feet)	by Hatfield Model (in
		feet)
4 Clusters in	140,000	17,000
Imlay, NV (aggregated)		