



Victoria Carter-Hall  
 Manager - Federal Regulatory

AT&T Services, Inc.  
 1120 20<sup>th</sup> St., NW, Suite 1000  
 Washington, DC 20036  
 T: 202.457.2164  
 F: 202.457.3072

RECEIVED

OCT 20 2014

Accepted/Files

October 2, 2014

Ms. Marlene H. Dortch, Secretary  
 Federal Communications Commission  
 445 12<sup>th</sup> Street, S.W.  
 Washington, DC 20554

FCC-Competition Policy Division  
 DOCKET FILE COPY ORIGINAL

OCT - 2 2014

Federal Communications Commission  
 Office of the Secretary

**Re: Certification of Public Notice of Network Change under Rule 51.329(a)  
CC Docket No. 96-98**

Dear Ms. Dortch:

Pursuant to the notification requirements in §51.325 -- §51.335 of the Commission's rules, AT&T hereby submits this certification of Public Notice of Network Change. A description of the network change is provided below:

Number	Type of Change Planned	Location of Change
ATT20141002L.1	BellSouth Telecommunications LLC. d/b/a AT&T Florida is announcing that in the Vernon wire center (VERNFLMA) Route 3, there will be a cutover of Central Office base copper circuits to proposed DLC and retire existing feeder fiber from Dawkins Rd along Highway 79 south to Clemmons Rd. Existing feeder copper cable will be lost during the DOT road widening project along Highway 79 from Dawkins Rd to Clemmons Rd. New DLC cabinets will be turned up on existing fiber cable and the existing Copper will be cut over to the proposed DLC cabinets. Cut over to the proposed DLC cabinet will allow for better cable relocation management and reduce the occurrences of service outages through the DOT road widening project plan. This plan will eliminate all loading and reduce the copper cable requirements for the overall project. The implementation date will not occur prior to June of 2015 in the 2 <sup>nd</sup> Qtr and could go into the 3 <sup>rd</sup> Qtr of 2015, so implementation will be shown as 2 <sup>nd</sup> and 3 <sup>rd</sup> Qtr 2015.	Vernon, FL

This notice is also available at: <https://ebiznet.att.com/networkreg/>

If you have any questions, please do not hesitate to contact me at (202) 457-2164.

Sincerely,

Victoria Carter-Hall

Attachments

CC: Carmell Weathers

**CERTIFICATION OF PUBLIC NOTICE(s) OF NETWORK  
CHANGE(s) UNDER RULE 51.329(a)**

On **October 2, 2014** the following Public Notice(s) of Network Change(s) have been made by **BellSouth Telecommunications, LLC**. Pursuant to Code of Federal Regulations 47, Subsections 51.325 – 51.335.



Richard R. Hatch  
Area Manager - Network Regulatory  
Telephone: (479) 253-7675      Date: 10/02/2014

The Public Notice(s) can also be obtained on the Internet at:

<https://ebiznet.att.com/networkreg/>

**Title(s) of Network Notification(s):**

**ATT20141002L.1**

PUBLIC NOTICE of NETWORK CHANGE UNDER RULE 51.329(a)

Network Disclosure Number: ATT20141002L.1 Issue Date: 10/02/2014  
 Modification Date: 2<sup>nd</sup> & 3<sup>rd</sup> Qtr 2015

Carrier's Name: BellSouth  
Telecommunications, LLC.  
d/b/a AT&T Florida

Carrier's Address: 135 Huntsville Rd, Eureka Springs, AR 72632

Contact: Your Account Manager or Service Representative  
**Technical Issues**  
 Richard Hatch  
 135 Huntsville Rd  
 Eureka Springs, AR 72632  
 479 253-7675  
rh4979@att.com

Public Notice: can be obtained on the Internet at:  
<https://ebiznet.att.com/networkreg/>

**Network Change:**

BellSouth Telecommunications LLC. d/b/a AT&T Florida is announcing that in the Vernon wire center (**VERNFLMA**) Route 3, there will be a cutover of Central Office base copper circuits to proposed DLC and retire existing feeder fiber from Dawkins Rd along Highway 79 south to Clemmons Rd. Existing feeder copper cable will be lost during the DOT road widening project along Highway 79 from Dawkins Rd to Clemmons Rd. New DLC cabinets will be turned up on existing fiber cable and the existing Copper will be cut over to the proposed DLC cabinets. Cut over to the proposed DLC cabinet will allow for better cable relocation management and reduce the occurrences of service outages through the DOT road widening project plan. This plan will eliminate all loading and reduce the copper cable requirements for the overall project. The implementation date will not occur prior to June of 2015 in the 2<sup>nd</sup> Qtr and could go into the 3<sup>rd</sup> Qtr of 2015, so implementation will be shown as 2<sup>nd</sup> and 3<sup>rd</sup> Qtr 2015.

**Description of Type of Changes Planned:**

It is proposed to cut the existing copper distribution facilities on Clemons Rd, Mallory Rd, and along Highway 79 from the intersection of Highway 79 and Mallory Rd to terminal F 4077 Hwy 79 ipid#51858. to proposed fiber fed DLC facilities and cross box in new DA311650.

**Description of Reasonably Foreseeable Impact of the Planned Changes:**

After this Plan is implemented and work is completed, metallic feeder facilities from the Central Office to the affected area will no longer be available. Unbundled loops that are defined as compatible with Digital Loop Carrier (DLC), e.g., those defined to transport POTS-grade service, will be transferred to the new DLC system without consequence. Competitive carriers employing unbundled loops that are defined to require metallic facilities, e.g., Digital Subscriber Line (DSL) or line sharing circuits will be notified individually. This notification is intended to allow the affected carrier to convert the circuit to one compatible with DLC. **Currently, there are no Competitive Carrier circuits of this type on the affected copper facilities.**

It should be noted that if a competitive carrier obtains an unbundled loop that has been defined to transport POTS-grade service, but then utilizes this loop to provide DSL service, AT&T will have no knowledge of the presence of DSL. In such a case, AT&T has no basis to notify the carrier and the ability of the competitive carrier to provide DSL service may be affected.

**Location of Change:**

CLLI Code/Statewide	City	State	Implementation Date
VERNFLMA	Vernon	FL	2 <sup>nd</sup> & 3 <sup>rd</sup> Qtr 2015